

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NW 1/4 NE 1/4 NE 1/4 2 T 30 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 2 MILES WEST OF SUBLETTE

2 WATER WELL OWNER: GARRETT-TRIBBEY, SUE ANN
 RR#, St. Address, Box #: 3620 SW STONEYBROOKE DR Board of Agriculture, Division of Water Resources
 City, State, ZIP code: TOPEKA, KS 66614- Application Number: 2,294 3,266 8,175

3 LOCATE WELL'S LOCATION WITH 4 DEPTH OF COMPLETED WELL 704 ELEVATION: 0
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 365 ft. below land surface measured on mo/day/yr 04/26/95
 Pump test data: Well water was 436 ft. after 4 hours pumping 620 gpm
 Estimated Yield 620 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 704 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 704 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 375 ft. to 475 ft., From 0 ft. to 0 ft.
 From 621 ft. to 701 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 704 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTH How many feet? 290

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	10	04 SANDY CLAY 07 FINE SAND			
10	46	04 SANDY CLAY 31 CALICHE			
46	66	01 CLAY 04 SANDY CLAY			
66	75	07 FINE SAND			
75	86	04 SANDY CLAY			
86	97	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
97	113	04 SANDY CLAY 31 CALICHE 05 SAND			
113	122	01 CLAY 04 SANDY CLAY			
122	141	07 FINE SAND 09 COARSE SAND 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 04/19/95 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/01/95
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 041 HASKELL NW 1/4 NE 1/4 NE 1/4 2 T 30 S R 33 W

2 WATER WELL OWNER: GARRETT-TRIBBEY, SUE ANN
RR#, St. Address, Box # : 3620 SW STONEYBROOKE DR Board of Agriculture, Division of Water Resources
City, State, ZIP code : TOPEKA, KS 66614- Application Number: 2,294

FROM	TO	LITHOLOGIC LOG
141	151	04 SANDY CLAY 05 SAND
151	185	07 FINE SAND 09 COARSE SAND 20 LIMESTONE
185	192	04 SANDY CLAY
192	368	08 MEDIUM SAND 13 FINE GRAVEL 15 CRS GRAVEL
368	370	20 LIMESTONE
370	380	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
380	386	20 LIMESTONE 07 FINE SAND 09 COARSE SAND
386	402	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
402	410	04 SANDY CLAY 20 LIMESTONE 05 SAND
410	415	05 SAND 13 FINE GRAVEL 15 CRS GRAVEL
415	442	04 SANDY CLAY 05 SAND
442	464	04 SANDY CLAY
464	474	04 SANDY CLAY
474	495	31 CALICHE 01 CLAY 20 LIMESTONE
495	512	19 SHALE 31 CALICHE 20 LIMESTONE
512	522	01 CLAY 19 SHALE 31 CALICHE
522	532	19 SHALE
532	620	19 SHALE
620	624	23 SANDSTONE
624	672	23 SANDSTONE 31 CALICHE 19 SHALE
672	701	23 SANDSTONE 31 CALICHE 19 SHALE
701	705	20 LIMESTONE
705	709	31 CALICHE 19 SHALE
709	720	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
completed on (mo/day/year) 04/19/95 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/01/95
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichman*