

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	1/4 1/4 NE 1/4	13	T 30 S	R 34 W

Distance and direction from nearest town or city street address of well if located within city?

NAVAHOE & PONCA STREETS SATANTA, KS

2 WATER WELL OWNER: CITY OF SATANTA

RR#, St. Address, Box #: PO BOX 665

City, State, ZIP code: SATANTA, KS 67870-0665

Board of Agriculture, Division of Water Resources

Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 460 ELEVATION: 0

Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 326 ft. below land surface measured on mo/day/yr 01/07/05

Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8 in. to 460 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 10 MONITORING

Was a chemical/bacteriological sample submitted to department? No;

If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: GLUED

Blank casing diameter 5 in. to 460 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 320 ft. to 460 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 460 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well?

How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	73	04 SANDY CLAY 01 CLAY			
73	81	07 FINE SAND 08 MEDIUM SAND			
81	98	04 SANDY CLAY 20 LIMESTONE			
98	173	05 SAND 13 FINE GRAVEL			
173	177	04 SANDY CLAY			
177	225	05 SAND 13 FINE GRAVEL			
225	233	01 CLAY			
233	306	05 SAND 13 FINE GRAVEL			
306	315	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/08/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/14/05 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	1/4 1/4 NE 1/4	13	T 30 S	R 34 W

2 WATER WELL OWNER: CITY OF SATANTA

RR#, St. Address, Box # : PO BOX 665

City, State, ZIP code : SATANTA, KS 67870-0665

Board of Agriculture, Division of Water Resources
Application Number:

FROM	TO	LITHOLOGIC LOG
315	377	05 SAND 13 FINE GRAVEL
377	378	01 CLAY
378	389	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
389	397	04 SANDY CLAY 05 SAND
397	430	07 FINE SAND 01 CLAY 20 LIMESTONE
430	438	01 CLAY
438	458	07 FINE SAND 01 CLAY
458	470	31 CALICHE
470	502	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/08/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/14/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichman*