

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>HASKELL</u>		<u>SE 1/4 SE 1/4 SW 1/4</u>	<u>27</u>	T <u>20</u> S	R <u>34</u> E/W
Distance and direction from nearest town or city street address of well if located within city? <u>Satanta - 2 1/2 SW on Hwy 56 - South & Southwest →</u>					
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # : <u>RFD 1</u>		Application Number:			
City, State, ZIP Code : <u>Rhyus, KS. 67870</u>					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>400</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL <u>190</u> ft. below land surface measured on mo/day/yr <u>5-6-98</u>			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm; Well water was ft. after hours pumping gpm			
		Bore Hole Diameter <u>12 1/4</u> in. to <u>20</u> ft., and <u>10 1/4</u> in. to <u>400</u> ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes..... No. <u>X</u> ; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes <u>X</u> No			
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)		5 Wrought iron	
2 PVC		4 ABS		6 Asbestos-Cement	
				7 Fiberglass	
Blank casing diameter <u>30</u> in. to <u>30</u> ft., Dia				8 Concrete tile	
Casing height above land surface <u>30</u> in., weight <u>200</u> lbs./ft.				9 Other (specify below)	
TYPE OF SCREEN OR PERFORATION MATERIAL:				CASING JOINTS: Glued <u>X</u> Clamped	
1 Steel		3 Stainless steel		7 PVC	
2 Brass		4 Galvanized steel		8 RMP (SR)	
				9 ABS	
SCREEN OR PERFORATION OPENINGS ARE:				10 Asbestos-cement	
1 Continuous slot		3 Mill slot <u>.032</u>		11 Other (specify)	
2 Louvered shutter		4 Key punched		12 None used (open hole)	
				8 Saw cut	
				9 Drilled holes	
				10 Other (specify)	
SCREEN-PERFORATED INTERVALS:		From <u>320</u> ft. to <u>340</u> ft.		From <u>360</u> ft. to <u>400</u> ft.	
		From ft. to ft.		From ft. to ft.	
GRAVEL PACK INTERVALS:		From <u>240</u> ft. to <u>400</u> ft.		From ft. to ft.	
		From ft. to ft.		From ft. to ft.	
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From <u>5</u> ft. to <u>26</u> ft., From <u>235</u> ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination: <u>NONE</u>					
1 Septic tank		4 Lateral lines		7 Pit privy	
2 Sewer lines		5 Cess pool		8 Sewage lagoon	
3 Watertight sewer lines		6 Seepage pit		9 Feedyard	
				10 Livestock pens	
				11 Fuel storage	
				12 Fertilizer storage	
				13 Insecticide storage	
				14 Abandoned water well	
				15 Oil well/Gas well	
				16 Other (specify below)	
Direction from well?				How many feet?	
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	Topsoil	384	390	coarse sand
1	6	Brown Sandy Clay & Caliche	390	398	Brown Clay
6	38	Sand & medium gravel	398	403	coarse sand
38	47	Tan Sandy Clay & Caliche	403	403	Tan Sandy Clay
47	91	Coarse Sand & small-large gravel			
91	98	Blue & Yellow Sandy Clay			
98	109	Large gravel & Red Gravel			
109	128	Tan Clay w/ sandstone & Large Gravel			
128	137	Tan Clay			
137	223	Coarse - Tan Gravel w/ Tan Clay streaks			
223	340	Coarse sand - large Tan Gravel			
340	351	Tan Clay			
351	356	Pink & white Sandy Clay			
356	365	coarse sand - small gravel			
365	384	Tan, white, Pink sandy clay w/ sandstone			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>5-6-98</u> and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. <u>KSA-600-A</u> This Water Well Record was completed on (mo/day/yr) <u>5-6-98</u>					
under the business name of <u>CRAMER DRIG Co.</u> by (signature) <u>Ray Cramer</u>					