

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>HASKELL</u>		<u>SE 1/4 SE 1/4 SE 1/4</u>	<u>32</u>	<u>T 30 S</u>	<u>R 34 E</u>
Distance and direction from nearest town or city street address of well if located within city? <u>Jct. 56 & 190 @ Santa - 5 mi. SW on Hwy 56 - Northeast →</u>					
2 WATER WELL OWNER: <u>Andrew Zanghi</u>		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # : <u>Rt 2 Box 84</u>		Application Number:			
City, State, ZIP Code: <u>Mos Santa, Ka. 67870</u>					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>340</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL <u>146</u> ft. below land surface measured on mo/day/yr <u>4-22-98</u>			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm; Well water was ft. after hours pumping gpm			
		Bore Hole Diameter <u>12 1/4</u> in. to <u>20</u> ft., and <u>9 1/4</u> in. to <u>350</u> ft.			
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well			
		<u>1 Domestic</u> 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No <u>X</u>; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? <u>Yes</u> No			
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued <u>X</u> Clamped <u>X</u>
2 PVC		4 ABS	6 Asbestos-Cement	9 Other (specify below)	Welded
			7 Fiberglass		Threaded
Blank casing diameter <u>5.56</u> in. to <u>280</u> ft. Dia. in. to ft. Dia. in. to ft.					
Casing height above land surface <u>30</u> in. weight <u>200</u> lbs./ft. Wall thickness or gauge No. <u>SDR-21 200psi</u>					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel		3 Stainless steel	5 Fiberglass	8 RMP (SR)	10 Asbestos-cement
2 Brass		4 Galvanized steel	6 Concrete tile	9 ABS	11 Other (specify)
					12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot		<u>3 Mill slot .035</u>	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
2 Louvered shutter		4 Key punched	6 Wire wrapped	9 Drilled holes	
			7 Torch cut	10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From <u>280</u> ft. to <u>340</u> ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From <u>240</u> ft. to <u>350</u> ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From <u>5</u> ft. to <u>26</u> ft., From ft. to ft., From <u>235</u> ft. to <u>240</u> ft.					
What is the nearest source of possible contamination:					
1 Septic tank		4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines		5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines		6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
				13 Insecticide storage	<u>Dog KENNELS</u>
Direction from well? <u>WEST</u>		How many feet? <u>140</u>			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	Topsoil			
4	14	Brown Sandy Clay			
14	56	Small-medium Gravel			
56	67	Yellow Sandy Clay w/ Rock			
67	76	Medium Gravel			
76	103	Coarse Sand / Yellow Sandy Clay			
103	315	Coarse Sand and Pea Gravel			
315	325	Tan Sandy Clay			
325	337	Sand and Gravel			
337	350	Red and Yellow Clay			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>4-22-98</u> and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. <u>KSA 600A</u> This Water Well Record was completed on (mo/day/yr) <u>5-2-98</u>					
under the business name of <u>Cramer Drilling Co.</u> by (signature) <u>Kelly Cramer</u>					