

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: 034 GRANT		SW 1/4 SW 1/4 NE 1/4	24	T 30 S	R 35 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 5 1/2 MILES WEST AND 1/2 SOUTH OF SATANTA

2 WATER WELL OWNER: CONNIE SAVAGE/DEAN HOCKETT		Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # : RT. 1, BOX 6	Application Number:	
City, State, ZIP code : SATANTA, KS 67870-		

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 380 ELEVATION: 0
	Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

1	2	3	4
5	6	7	8
9	10	11	12
13	14	15	16
17	18	19	20
21	22	23	24

NW NE
W X E
SW SE

WELL'S STATIC WATER LEVEL 165 ft. below land surface measured on mo/day/yr 05/21/93

Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 10 in. to 380 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: ~~OTHER~~ *Domestic (stock)*

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED	
Blank casing diameter 5 in. to 380 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. .327	
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC	
SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT	

SCREEN PERFORATED INTERVALS:	From 380 ft. to 380 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 380 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE	
Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: NONE OBSERVED	
Direction from well?	How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	04 SANDY CLAY			
2	118	09 COARSE SAND 14 MED GRAVEL 16 V CRS GRAVEL			
118	122	01 CLAY			
122	150	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
150	155	01 CLAY			
155	165	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
165	178	01 CLAY			
178	181	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
181	210	01 CLAY 20 Limestone 07 FINE SAND			
210	378	08 MEDIUM SAND 09 COARSE SAND 15 CRS GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas	
Water Well Contractor's License No. 145	This Water Well Record was completed on (mo/day/yr) 05/29/93
under the business name of HENKLE DRILLING & SUPPLY	by (signature)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 034 GRANT	SW 1/4 SW 1/4 NE 1/4	24	T 30 S	R 35 W

12 WATER WELL OWNER: CONNIE SAVAGE%DEAN HOCKETT
1 RR#, St. Address, Box # : RT. 1, BOX 6
1 City, State, ZIP code : SATANTA, KS 67870-
Board of Agriculture, Division of Water Resources
Application Number:

FROM	TO	LITHOLOGIC LOG
378	384	01 CLAY

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
1 completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas
1 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/29/93
1 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichmuth*