

WATER WELL RECORD Form #WC-5 PSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 034 GRANT SE 1/4 NE 1/4 NW 1/4 21 T 30 S R 37 W

Distance and direction from nearest town or city street address of well: if located within city?
 APPROX. 10 1/4 MILES SOUTH & 1/2 MILE WEST OF ULYSSES.

2 WATER WELL OWNER: ANDERSON, DORIS
 RR#, St. Address, Box #: 118 N. JACKSON Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUGOTON, KS 67951- Application Number: 7,997

3 LOCATE WELL'S LOCATION WITH 4 DEPTH OF COMPLETED WELL 518 ELEVATION: 0
 AS "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 235 ft. below land surface measured on mo/day/yr 05/25/96
 Pump test data: Well water was 280 ft. after 4 hours pumping 710 gpm
 Estimated Yield 710 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 518 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Has a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 518 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 265 ft. to 325 ft., From 358 ft. to 378 ft.
 From 334 ft. to 344 ft., From 405 ft. to 515 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 518 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? *SOUTHWEST* How many feet? 775

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	45	04 SANDY CLAY			
45	80	01 CLAY 07 FINE SAND			
80	165	01 CLAY			
165	210	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
210	265	08 MEDIUM SAND 09 COARSE SAND 01 CLAY			
265	280	09 COARSE SAND 13 FINE GRAVEL			
280	300	08 MEDIUM SAND 09 COARSE SAND 01 CLAY			
300	325	08 MEDIUM SAND 09 COARSE SAND			
325	335	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was
 completed on (mo/day/year) 05/21/96 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/20/96
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form #WC 5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 034 GRANT	SE 1/4 NE 1/4 NW 1/4	21	T 30 S	R 37 W

2 WATER WELL OWNER:	ANDERSON, DORIS	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	118 N. JACKSON	Application Number: 7,997
City, State, ZIP code :	HUGOTON, KS 67951-	

FROM	TO	LITHOLOGIC LOG
335	342	08 MEDIUM SAND 09 COARSE SAND
342	360	01 CLAY 07 FINE SAND 08 MEDIUM SAND
360	375	23 SANDSTONE
375	378	LOST CIRCULATION
378	402	19 SHALE
402	423	19 SHALE 23 SANDSTONE
423	442	19 SHALE 23 SANDSTONE
442	515	19 SHALE 23 SANDSTONE
515	520	28 ROCK

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 05/21/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's license No. 145 This Water Well Record was completed on (mo/day/yr) 06/20/96 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Benny Reichert*