


1 LOCATION OF WATER WELL:		Fraction SW 1/4 NW 1/4 NW 1/4		Section Number 10	Township Number T 30 S	Range Number R 37 EW
County: Grant						
Distance and direction from nearest town or city street address of well if located within city? From Ulysses - 8 1/4 Miles South - East side of road						
2 WATER WELL OWNER:		Kansas Power & Light				
RR#, St. Address, Box # :		P. O. Box 8568				
City, State, ZIP Code :		Pratt, Kansas 67124				
Board of Agriculture, Division of Water Resources Application Number: 913						
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 500 ft. ELEVATION:				
		Depth(s) Groundwater Encountered 1. NA ft. 2. . ft. 3. . ft.				
		WELL'S STATIC WATER LEVEL 246 ft. below land surface measured on mo/day/yr 2-24-89				
		Pump test data: Well water was . ft. after . hours pumping . gpm				
		Est. Yield . gpm: Well water was . ft. after . hours pumping . gpm				
		Bore Hole Diameter 30 in. to 500 ft. and . in. to . ft.				
		WELL WATER TO BE USED AS:				
		5 Public water supply 8 Air conditioning 11 Injection well				
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)				
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well				
		Was a chemical/bacteriological sample submitted to Department? Yes X No .; If yes, mo/day/yr sample was submitted				
		Water Well Disinfected? Yes X No				
5 TYPE OF BLANK CASING USED:						
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued . Clamped .						
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded X						
Blank casing diameter 12 in. to 350 ft. Dia. 12 in. to 500 ft. Dia. . in. to . ft.						
Casing height above land surface 12 in. weight 29.28 lbs./ft. Wall thickness or gauge No. .219						
TYPE OF SCREEN OR PERFORATION MATERIAL:						
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement						
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) .						
SCREEN OR PERFORATION OPENINGS ARE:						
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)						
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes						
7 Torch cut 10 Other (specify) .						
SCREEN-PERFORATED INTERVALS: From 350 ft. to 490 ft. From . ft. to . ft.						
From . ft. to . ft. From . ft. to . ft.						
GRAVEL PACK INTERVALS: From 25 ft. to 500 ft. From . ft. to . ft.						
From . ft. to . ft. From . ft. to . ft.						
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other .						
Grout Intervals: From 5 ft. to 25 ft. From . ft. to . ft. From . ft. to . ft.						
What is the nearest source of possible contamination:						
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well						
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well						
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)						
13 Insecticide storage						
Direction from well? West How many feet? 50						
FROM	TO	LITHOLOGIC LOG		FROM	TO	PLUGGING INTERVALS
		See attached log				
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 2-24-89 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 208 This Water Well Record was completed on (mo/day/yr) 6-12-89 under the business name of Minter-Wilson Drilling Co., Inc. by (signature) <i>Mara Kellu</i>						

The
Professionals

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

Kansas Power & Light Gas Service
Grant County
12-22-88

Location: NW $\frac{1}{4}$ 10-30-37
From Ulysses - 8 $\frac{1}{2}$ S. - E. Side of road
50' E. of well

Static Water Level - about 320'

Test #1

0	3	Top soil
3	66	Brown sandy clay
66	82	Brown clay
82	97	Fine sand
97	174	Brown clay
174	188	Brown clay small strip of gravel mixed
188	222	Gray clay
222	246	Brown sandy clay
246	263	Fine to medium sand & gravel - loose
263	293	Fine to medium sand & gravel - 20% clay
293	328	Brown sandy clay
328	341	Fine to medium
341	350	Brown sandy clay
350	277	Fine sand - 25% clay
377	390	Brown sandy clay
390	430	Red yellow clay
430	443	Sand stone - 10% clay
443	455	Sand stone - 20% clay
455	485	Sand stone - loose
485	490	Yellow brown & red clay - 10% sand stone-tight
490	515	Red bed - tight
515	545	Red bed - hard