


USE TYPEWRITER OR BALL
POINT PEN—PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Grant	Township name Sullivan	Fraction SW 1/4 SE 1/4 SE 1/4	Section number 10	Town number 30S	Range number 37W	
Distance and direction from nearest town or city: 9 miles south of Ulysses, Ks. Street address of well location if in city:				3 Owner of well: Henrietta Spencer Address: 1293 Martin Ave. Palo Alto, Calif.			
Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		4 Well depth: 523.5 ft. Date of completion 7-13-75 Well diameter 27 in.			
2 Type and color of material		From		To		5 ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
						6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well ☐	
Surface		0		2		7 Casing: Material stl Height: above below Threaded ☐ Welded ☒ Surface ☐ in. Diam. 17 1/2" Weight 36.8 lbs./ft. 1 0 in. to 251.10 ft. depth Drive shoe? ☐ Yes ☒ No	
Sandy clay w/fine sand strips		2		50		8 Screen: Lakewood Manufacturer steel Dia. 16" Type 3/16" Length 2" slot Set between 251.10 and 523.5	
Brown sandy clay w/fine sand strips		50		213		Fittings: 1 1/2 x 5/8 Gravel pack ☒ Yes ☐ No Size range of material —	
Medium to coarse sand		213		221		9 Static water level: 201 ft. below land surface Date 7-12-75	
Embedded sand & clay w/loose strips		221		238		10 Pumping level below land surfaces: ft. after — hrs. pumping — g.p.m. 350 ft. after 49.8 hrs. pumping 1000 g.p.m. Estimated maximum yield 1000 g.p.m.	
Medium to coarse sand w/clay breakers		238		255		11 Water sample submitted: ☐ Yes ☒ No Date —	
Medium to coarse sand w/clay breakers		30 ft 255		289		12 Well head completion: ☐ Pitless adapter ☒ 12 inches above grade	
Embedded sand & clay		289		309		13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ Depth: From 0 ft. to 10 ft.	
Medium to coarse sand		25 ft 309		336		14 Nearest source of possible contamination: ft. 300 Direction NW Type House Well disinfected upon completion? ☐ Yes ☐ No	
Medium to coarse sand w/clay tight		336		346		15 Pump: ☒ Not installed Manufacturer's name — Model number — HP — Volts — Length of drop pipe — ft. capacity — g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
Sandy clay w/fine to medium sand		6 ft 346		360			
Sandy clay w/very fine sand strips		360		425			
Yellow chalk, gray clay, cheyenne		8 ft 425		438			
Brown shale w/cheyenne & Dakota		10 ft 438		453			
Brown shale w/cheyenne & Dakota		7 ft 453		480			
Brown shale, sandrock, cheyenne and Dakota		5 ft 480		506			
Brown shale, sandrock, cheyenne and Dakota		25 ft 506		529			
(use a second sheet if needed)							
16 Remarks: elevation Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Houck Bros. Drlg. Co. 164 Business name Box 487, Ulysses, Ks. Address M. Beard Date 8-15-75 Signed — Authorized representative			

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5