

[1] LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: GRANT		SE ¼ SW ¼ SE ¼	15	T 30S S	R 37W E/W
Distance and direction from nearest town or city street address of well if located within city? 10 MILES SOUTH OF ULYSSES, KS					
[2]	WATER WELL OWNER: OXY USA, INC.			#1 mlp dollar A	
RR#, St. Address, Box # : BOX 26100			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : OKLAHOMA CITY, OK 73126-0100			Application Number: 930367		
[3]	LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: N --- NW --- NE --- W [] E --- SW --- SE --- S ↑ 1 Mile ↓ X	[4]	DEPTH OF COMPLETED WELL .340 ft. ELEVATION: Depth(s) Groundwater Encountered 1. 210 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL .210 ft. below land surface measured on mo/day/yr 9-20-93 Pump test data: Well water was 225 ft. after 1 hours pumping 100 gpm Est. Yield .100 gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter .11 in. to .340 ft., and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot ⑥ Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes.....No...X..... If yes, mo/day/yr sample was submitted _____ Water Well Disinfected? Yes X No		
[5]	TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) ② PVC 4 ABS Blank casing diameter .6 in. to .340 ft., Dia in. to ft., Dia in. to ft. Casing height above land surface .24 in., weight 2.902 lbs./ft. Wall thickness or gauge No. .280 SDR 21 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped ⑧ Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 3 Torch cut 10 Other (specify) _____ SCREEN-PERFORATED INTERVALS: From .240 ft. to .340 ft., From ft. to ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From .205 ft. to .340 ft., From ft. to ft. From ft. to ft., From ft. to ft.				
[6]	GROUT MATERIAL: ① Neat cement 2 Cement grout 3 Bentonite ④ Other HOLE PLUG Grout Intervals: From ft. to ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage ⑮ Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage Direction from well? SOUTHEAST How many feet? 95				
		LITHOLOGIC LOG	PLUGGING INTERVALS		
FROM	TO		FROM	TO	
0	20	TOP SOIL & CLAY			
20	40	CLAY			
40	160	SANDY CLAY			
160	220	FINE SAND & CLAY MIX			
220	300	FINE TO COARSE Sand & little Clay			
300	330	FINE TO COARSE SAND			
330	340	SANDY CLAY			
[7] CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ① constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 9-20-93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. KWWCL-430 This Water Well Record was completed on (mo/day/yr) 9-20-93 under the business name of HOWARD DR LG.CO.BOX 806 BEAVER,OK 73932 by (signature)					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					