

HW-2

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Grant	NE 1/4 NW 1/4 NW 1/4	25	T 30 S	R 38 E (N)

Distance and direction from nearest town or city street address of well if located within city? **West**
8 miles South of Ulysses, then 4 miles ~~South of Ulysses, then 4 miles~~ **MW-2**

2 WATER WELL OWNER:	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	Application Number:
City, State, ZIP Code :	

LOREN WITT
608 N. WEST ST.
Wichita, KS 67203

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 250 ft. ELEVATION:
	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL 225.97 ft. below land surface measured on mo/day/yr 12-2-94
	Pump test data: Well water was ft. after hours pumping gpm
	Est. Yield gpm: Well water was ft. after hours pumping gpm
	Bore Hole Diameter 7 7/8 in. to ft., and in. to ft.
WELL WATER TO BE USED AS:	
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well	
Was a chemical/bacteriological sample submitted to Department? Yes (No) ; If yes, mo/day/yr sample was submitted	
Water Well Disinfected? Yes (No)	

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	Welded
Blank casing diameter 4 in. to 0.5 ft., Dia 4 in. to 220 ft., Dia in. to ft.			Threaded (PVC)
Casing height above land surface in., weight lbs./ft. Wall thickness or gauge No.			
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
10 Asbestos-cement	11 Other (specify)	12 None used (open hole)	
SCREEN OR PERFORATION OPENINGS ARE:			
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	8 Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes
7 Torch cut	10 Other (specify)	11 None (open hole)	
SCREEN-PERFORATED INTERVALS: From 250 ft. to 220 ft., From ft. to ft.			
GRAVEL PACK INTERVALS: From 220-250 ft. to 218 ft., From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From 216 ft. to 225 ft., From ft. to ft., From ft. to ft.				
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well? West How many feet? 98'				

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	0.5	Topsoil	218'	216'	Bentonite pellets
0.5	58'	Silty clay, low plasticity			
58'	78'	Clay, med. plasticity			
78'	98'	Clayey sand, low plasticity			
98'	108'	Clay, medium plasticity			
108'	128'	Clayey sand, low plasticity			
128'	168'	Sand, medium to FINE, well graded			
168'	188'	Sand, medium, poorly graded			
188'	198'	Clayey sand, low plasticity			
198'	208'	Clay, medium plasticity			
208'	218'	Clayey sand, low plasticity			
218'	250'	Clay, medium plasticity			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 11-16-94 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 438 This Water Well Record was completed on (mo/day/yr) 12-4-94
under the business name of Huntingdon by (signature) Bernie Lone