

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

1 Location of well:	County <b>Stanton</b>	Township name <b>NA</b>	Fraction <b>SW SW NE</b>	Section number <b>28</b>	Town number <b>30S</b>	Range number <b>39W</b>
Distance and direction from nearest town or city: <b>10 miles south, 1 west, 1/2 south of Big Bow, Kansas</b> <small>Street address of well location if in city:</small>				3 Owner of well: <b>Maude Collingwood, Trust</b> Address: <b>% Dave Wilson</b> <b>Meade, Kansas</b>		
Locate with "X" in section below: N		Sketch map:				
2 Type and color of material			From	To	4 Well depth: <b>370.6</b> ft. Date of completion: <b>4-8-75</b> Well diameter <b>27</b> in.	
<b>Surface</b>			0	2	5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
<b>Sandy clay</b>			2	90	6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input type="checkbox"/>	
<b>Sandy clay &amp; lime shale</b>			90	115	7 Casing: Material <b>steel</b> Height: <b>above</b> /below Threading <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. Dia. <b>16"</b> Weight <b>36.8</b> lbs./ft. <b>1</b> 0 in. to <b>220.11</b> ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No in. to in. ft. depth!	
<b>Brown clay</b>			115	158	8 Screen: Manufacturer <b>Lakewood</b> Type <b>steel</b> Dia. <b>16"</b> <b>Slot</b> gauze <b>3/16</b> Length <b>2" slot</b> Set between <b>220.11</b> ft. and <b>370.6</b> ft. Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <b>1/4 x 5/8</b>	
<b>Sandy clay w/sand strips</b>			158	167	9 Static water level: <b>146</b> ft. below land surface Date <b>4-5-75</b>	
<b>Medium to coarse sand w/clay breakers</b>			167	178	10 Pumping level below land surfaces: <b>199</b> ft. after <b>6.5</b> hrs. pumping <b>1461</b> g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield <b>1800</b> g.p.m.	
<b>Brown gummy clay</b>			178	211	11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date	
<b>Sandy clay w/medium sand strips 2-1-1-1 5 ft.</b>			211	223	12 Well head completion: <input type="checkbox"/> Pitless adapter <b>12</b> Inches above grade	
<b>Medium to coarse sand w/clay breakers 19 ft.</b>			223	249	13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Depth: From <b>0</b> ft. to <b>10</b> ft.	
<b>Brown &amp; sandy clay w/sand strips &amp; sandrock</b>			249	307	14 Nearest source of possible contamination: <b>Church</b> ft. <b>3/4</b> direction <b>N.</b> Type <b>Church</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No	
<b>Meidum to coarse sandrock w/clay breakers 46 ft.</b>			307	359	15 Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.m.p. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
<b>Yellow chalk, loose sandrock &amp; Dakota 5 ft.</b>			359	384	17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Houck Bros. Drlg. Co. 164</b> Business name <b>BOX 487, Ulysses, KS.</b> License No. Address <b>M. Beard</b> Date <b>4-22-75</b> Signed _____ Authorized representative	
16 Remarks: elevation <b>Drilled in plowed field</b>						
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						