

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1		LOCATION OF WATER WELL:		FRACTION	TOWNSHIP NUMBER	RANGE NUMBER
		Sumner		NW 1/4 NW 1/4 NW 1/4	10 T 30 S	R 4W E/W
Distance and direction from nearest town or city street address of well if located within city? 1623 W. 140th 1/2 E. of Suppesville & K-42 Milton Rd. Milton, Kansas						
2		WATER WELL OWNER: RR#,ST. ADDRESS,BOX #: CITY, STATE:		Board of Agriculture, Division of Water Resource GEORGE, MIKE CONSTRUCTION 1717 Elk Ridge Goddard, Kansas		
				ZIP CODE:	Application Number:	
3		LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: N NW ——— NE SW ——— SE S		4		
				DEPTH OF COMPLETED WELL: 80 ft. ELEVATION:		
				Depth of groundwater Encountered: _____ ft.		
				WELL'S STATIC WATER LEVEL 15 FT. BELOW LAND SURFACE MEASURED ON mo/day/yr: 1/26/11		
				Pump test data: Well water was _____ ft. after _____ hours of pumping @ _____ gpm		
				Est. Yield: _____ gpm Well water was _____ ft. after _____ hours of pumping @ _____ gpm		
				Bore Hole Diameter 12 in. to 80 ft. and _____ in. to _____ ft.		
				WELL WATER TO BE USED AS:		
				☒ 1. Domestic ☐ 3. Feedlot ☐ 5. Public water supply ☐ 7. Lawn and garden only ☐ 9. Dewatering ☐ 11. Injection well		
				☐ 2. Irrigation ☐ 4. Industrial ☐ 6. Oil field water supply ☐ 8. Air conditioning ☐ 10. Monitoring well ☐ 12. Other (Specify below)		
				Was a chemical/bacteriological sample submitted to Department? YES ☒ NO ☐ ; If yes, what mo/day/yr was sample submitted _____		
				Was Water Well Disinfected? YES ☒ NO ☐		
5		TYPE OF CASING USED:		CASING JOINTS: ☒ Glued Threaded		
		1. Steel 3. RPM (SR)		Welded Clamped		
		☒ 2. PVC 4. ABS				
		5. Wrought Iron 7. Fiberglass		SDR-26		
		Blank casing diameter 5 in. to 28 ft., Dia. _____ in. to _____ ft., Dia. _____ in. to _____ ft.				
		Casing height above land surface: 12 in., Weight: 2.35 lbs. / ft. Wall thickness or gauge No. .214				
		TYPE OF SCREEN OR PERFORATION MATERIAL:				
		1. Steel 3. Stainless Steel 5. Fiberglass		☒ 7. PVC		
		2. Brass 4. Galvanized 6. Concrete Tile		9. ABS 11. Other (specify)		
		SCREEN OR PERFORATION OPENINGS ARE:		10. Asbestos-Cement 12. None used (open hole)		
		1. Continuous slot 3. Mill slot 5. Gauzed wrapped		7. Torch cut 9. Drilled holes 11. None (open hole)		
		2. Louvered shutter 4. Key punched 6. Wire wrapped		☒ 8. Saw cut 10. Other (specify)		
		SCREEN - PERFORATION INTERVAL From 28 ft. to 80 ft., From _____ ft. to _____ ft., GRAVEL PACK INTERVALS: From 24 ft. to 80 ft., From _____ ft. to _____ ft.				
6		GROUT MATERIALS: 1. Neat cement 2. Cement Grout 3. Bentonite Other bentonite hole plug				
		Grout Intervals: From 4 ft. to 24 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.				
		What is the nearest source of possible contamination:				
		1. Septic tank 4. Lateral lines 7. Pit privy 10. Livestock pens 13. Insecticide storage 15. Oil well/Gas well				
		2. Sewer lines 5. Cess Pool 8. Sewage lagoon 11. Fuel storage 14. Abandon water well 16. Other (specify below)				
		3. Watertight sewer line 6. Seepage pit 9. Feed yard 12. Fertilizer storage		None Yet		
		Direction from well?		How many feet?		
		From To LITHOLOGIC LOG		From To LITHOLOGIC LOG		
		0 3 topsoil				
		3 12 clay				
		12 18 fine sand				
		18 22 sandy clay				
		22 50 gray shale				
		50 60 red shale				
		60 80 gray shale				
7		Contractor's or Landowner's Certification: This water well was 1. ☒ constructed 2. reconstructed or 3. plugged under my jurisdiction and was completed on (mo/day/year) 1/26/2011 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This water well record was completed on (mo/day/year) 1/28/2011 under the business name of Harp Well and Pump Service by (signature) <i>Todd S. Harp</i>				