

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Sumner		SW 1/4 SW 1/4 NE 1/4	26	T 30 S	R 4 E (W)
Distance and direction from nearest town or city street address of well if located within city? 5W 1N 1/2E 1/2N OF CONWAY SPRINGS, KS					
2 WATER WELL OWNER: H-30 Drilling Co.					
RR#, St. Address, Box # : 251 N. Water Suite 10			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : Wichita, Kansas 67202			Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 26 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 6 ft. 2. 6 ft. 3. 6 ft.			
		WELL'S STATIC WATER LEVEL 5 ft. below land surface measured on mo/day/yr 7-25-82			
		Pump test data: Well water was 25 gpm: Well water was 26 ft. after 25 hours pumping 25 gpm			
		Bore Hole Diameter 10 in. to 26 ft., and 26 in. to 26 ft.			
WELL WATER TO BE USED AS:					
1 Domestic 3 Feedlot ⑥ Oil field water supply 9 Dewatering 11 Injection well 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well 12 Other (Specify below)					
Was a chemical/bacteriological sample submitted to Department? Yes.....No..... X; If yes, mo/day/yr sample was submitted					
Water Well Disinfected? Yes X No					
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped ② PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded 7 Fiberglass Threaded					
Blank casing diameter 5 in. to 11 ft., Dia 11 in. to 11 ft., Dia 11 in. to 11 ft.					
Casing height above land surface 12 in., weight 12 lbs./ft. Wall thickness or gauge No. 214					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass ⑦ PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped ⑧ Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 11 ft. to 26 ft., From 11 ft. to 26 ft., From 11 ft. to 26 ft.					
GRAVEL PACK INTERVALS: From 10 ft. to 26 ft., From 10 ft. to 26 ft., From 10 ft. to 26 ft.					
6 GROUT MATERIAL: ① Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From 0 ft. to 10 ft., From 0 ft. to 10 ft., From 0 ft. to 10 ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) NONE 13 Insecticide storage					
Direction from well? How many feet?					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	2	Top soil			
2	6	Clay, tan			
6	14	Sand, fine to med			
14	17	Clay, light tan with fine sand			
17	30	Shale, red and blue			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ① constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 25 July 82 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 325 This Water Well Record was completed on (mo/day/yr) 25 Oct 82 under the business name of Central Well & Pump Inc. by (signature) John A. ...					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					