



Form	WWC5
Contractor	Downey Drilling, Inc.
Well Owner	GEORGE E PEPPERCORN
Doc ID	1308802

Litholgy

From	To	LithologicLog
0	1	TOPSOIL & SILT
1	47	SILT W/ SANDY CLAY
47	66	M/C SAND & TR. F. GRAVEL
66	67	MAG
67	70	M/C SAND & TR. F. GRAVEL
70	86	SANDY CLAY W/ SILT
86	102	SANDY CLAY W/ MAG
102	114	SANDY CLAY W/ SAND LENSES
114	120	SANDY CLAY W/ SAND STRS
120	177	SANDY CLAY W/ MAG & SAND STRS
177	183	M/ TR C/ SAND W/ SANDY CLAY
183	197	SANDY CLAY / M. SAND
197	200	SANDY CLAY/CEM SAND
200	201	SANDY CLAY
201	206	SANDY CLAY W/ MED SAND LENSES
206	208	M/C SAND
208	209	SILT
209	218	F/C SAND & F/M GRAVEL
218	221	SANDY CLAY
221	246	C. SAND & F. GRAVEL
246	248	SILT

Form	WWC5
Contractor	Downey Drilling, Inc.
Well Owner	GEORGE E PEPPERCORN
Doc ID	1308802

Litholgy

From	To	LithologicLog
248	260	C. SAND & F. GRAVEL
260	264	SILT/SANDY CLAY
264	266	M/C SAND
266	276	VERY C. SAND / F/M GRAVEL & TR. CEM SAND
276	290	SANDY CLAY W/ TR. MAG
290	292	C. SAND
292	303	F/M GRAVEL
303	305	SILT/SANDY CLAY
305	306	C/VC SAND
306	308	SILT & SANDY CLAY
308	328	SAND & F/TR MED GRAVEL
328	335	SANDY CLAY
335	337	SANDY CLAY W/ MAG STRIPS
337	340	SANDY CLAY & CLAY
340	344	SANDY CLAY W/ TR. MAG
344	350	F/M SAND
350	360	TR. C SAND
360	380	F/C SAND & TR. F GRAVEL
380	385	F/TR MED GRAVEL W/ BRWN ROCK
385	397	SANDY CLAY & SHALE
397	398	SILTSTONE
398	406	CLAY & SHALE

Form	WWC5
Contractor	Downey Drilling, Inc.
Well Owner	GEORGE E PEPPERCORN
Doc ID	1308802

Litholgy

From	To	LithologicLog
406	407	LIMESTONE
407	413	SHALE
413	420	SHALE W/ F. SAND LENSES
420	426	SHALE W/ TR. VERY F. SAND
426	427	LIMESTONE
427	440	FINE SAND
440	451	VERY F. SAND -DAKOTA W/ THIN SHALE
451	454	SHALE
454	460	SHALE
460	471	SHALE
471	472	F. SAND & SANDSTONE
472	480	V. FINE SAND & SANDSTONE
480	489	VERY FINE SAND
489	500	V., FINE SAND & SANDSTONE/ GRAY VOLCANIC ASH LENSES
500	538	V. FINE SAND & SANDSTONE & DAKOTA
538	546	SHALE CLAY
546	572	V. FIN SAND & SANDSTONE
572	583	SHALE & WHITE CLAY
583	594	RED CLAY & SILTSTONE