

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: STANTION SW 1/4 SW 1/4 SW 1/4 13 T 30 S R 41 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM JOHNSON - 9 SOUTH ON HIGHWAY 27

2 WATER WELL OWNER: LOVE, FRED  
 RR#, St. Address, Box #: PO BOX 545 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: JOHNSON, KS 67855- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

	NW	NE	
W			E
	SW	SE	

4 DEPTH OF COMPLETED WELL 553 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 197 ft. below land surface measured on mo/day/yr 07/18/05  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 12 in. to 553 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CLAMPED  
 Blank casing diameter 6 in. to 553 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 0.025  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 448 ft. to 548 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 553 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BBNTONITE  
 Grout intervals: From 4 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: ABANDONED WELL  
 Direction from well? EAST How many feet? 60

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY			
20	40	05 CLAY 02 FINE SAND 35 CALACHIE			
40	60	35 CALACHIE 37 PIN-COAR SAN			
60	80	37 PIN-COAR SAN			
80	100	05 CLAY 35 CALACHIE			
100	120	05 CLAY 35 CALACHIE 02 FINE SAND			
120	140	02 FINE SAND 05 CLAY 19 LAYERS			
140	160	02 FINE SAND 05 CLAY			
160	180	10 FINE-MEDSAND			
180	200	37 PIN-COAR SAN			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/20/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 08/02/05 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Josid Crick*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:      Fraction      Section Number      Township Number      Range Number  
COUNTY: STANTION      SW    1/4 SW    1/4 SW    1/4      13      T 30      S      R 41      W

2 WATER WELL OWNER:      LOVE, FRED  
RR#, St. Address, Box #:      PO BOX 545      Board of Agriculture, Division of Water Resources  
City, State, ZIP code :      JOHNSON, KS      67855-      Application Number:

FROM	TO	LITHOLOGIC LOG
200	220	02 FINE SAND 29 SANDSTONE (Tan)
220	240	29 SANDSTONE (Tan)
240	300	29 SANDSTONE 07 BLUE SHALE (Tan)
300	320	07 BLUE SHALE 08 ROCK LAYERS
320	340	29 SANDSTONE 16 GRAY CLAY
340	360	16 GRAY CLAY 29 SANDSTONE 26 RED CLAY
360	540	29 SANDSTONE
540	560	29 SANDSTONE (Red)

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/20/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179      This Water Well Record was completed on (mo/day/yr) 08/02/05 under the business name of JOB'S WELL SERVICE, INC.      by (signature) *Judith Creek*