

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: STANTION NW 1/4 NE 1/4 NE 1/4 2 T 30 S R 42 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM HANTER - 2 1/2 S ON BLACK TOP - 1/2 E AND 1/2 SOUTH

2 WATER WELL OWNER: BOZONE, DAVID
 RR#, St. Address, Box #: HC 02 -- BOX 64 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: ROLLA, KS 67954- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

		X	
1	NW	NE	
Mile			E
W			
	SW	SE	

4 DEPTH OF COMPLETED WELL 365 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 146 ft. below land surface measured on mo/day/yr 04/01/98
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 15 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 365 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 365 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 300 ft. to 360 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 365 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	40	CLAY FINE - MED SAND			
40	60	FINE - MED SAND SMALL GRAVEL CLAY			
60	80	CLAY THIN ROCK LAYER			
80	100	CLAY THIN ROCK LAYER			
100	140	CLAY TAN IN COLOR THIN ROCK LAYER			
140	160	SANDSTONE TAN IN COLOR CLAY LAYERS			
160	230	SANDSTONE TAN IN COLOR			
230	240	ROCK GRAY CLAY			
240	300	CLAY BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 04/01/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 04/14/98 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joseph C. ...*

RECEIVED

JUN

BUREAU

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: STANTION NW 1/4 NE 1/4 NE 1/4 2 T 30 S R 42 W

2 WATER WELL OWNER: BOZONE, DAVID
 RR#, St. Address, Box #: HC 02 -- BOX 64 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: ROLLA, KS 67954- Application Number:

FROM	TO	LITHOLOGIC LOG
300	360	SANDSTONE
360	380	RED CLAY ROCK LAYERS SHALE (Red)