


1 LOCATION OF WATER WELL: County: Kingman		Fraction SE 1/4 NW 1/4 SW 1/4	Section Number 9	Township Number T 30 S	Range Number R 8 EW																																				
Distance and direction from nearest town or city street address of well if located within city? 1 3/4 W 1/4 N OF SPIVEY, KS																																									
2 WATER WELL OWNER: B H M V Co. RR#, St. Address, Box # : Spivey, Kansas City, State, ZIP Code :			Board of Agriculture, Division of Water Resources Application Number: 35,670																																						
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: 57 ft. ELEVATION: Depth(s) Groundwater Encountered 1. 10 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 10 ft. below land surface measured on mo/day/yr 30 Sept. 82 Pump test data: Well water was 25 ft. after 1 hours pumping 300 gpm Est. Yield gpm Well water was 31 ft. after 1 hours pumping 400 gpm Bore Hole Diameter 27 in. to 57 ft. and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 11 Injection well 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well Was a chemical/bacteriological sample submitted to Department? Yes..... No X If yes, mo/day/yr sample was sub- mitted Water Well Disinfected? Yes X No																																							
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 2 PVC 4 ABS Blank casing diameter 12 in. to 17 ft., Dia in. to ft., Dia in. to ft. Casing height above land surface 12 in., weight lbs./ft. Wall thickness or gauge No. 140		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped 6 Asbestos-Cement 9 Other (specify below) Welded X 7 Fiberglass Threaded TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 10 GAUGE 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) SCREEN-PERFORATED INTERVALS: From 17 ft. to 57 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 10 ft. to 57 ft., From ft. to ft.																																							
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From 0 ft. to 10 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) NONE 13 Insecticide storage Direction from well? How many feet?																																									
<table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th></tr></thead><tbody><tr><td>02</td><td>2</td><td>Soil, sandy</td><td></td><td></td><td></td></tr><tr><td>2</td><td>10</td><td>Sand, med to coarse and med gravel, loose</td><td></td><td></td><td></td></tr><tr><td>10</td><td>40</td><td>Sand, fine to coarse and fine to med gravel, loose with some silty spots</td><td></td><td></td><td></td></tr><tr><td>40</td><td>57</td><td>Sand, med to coarse and med to coarse gravel</td><td></td><td></td><td></td></tr><tr><td>57</td><td>60</td><td>Shale, red</td><td></td><td></td><td></td></tr></tbody></table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG	02	2	Soil, sandy				2	10	Sand, med to coarse and med gravel, loose				10	40	Sand, fine to coarse and fine to med gravel, loose with some silty spots				40	57	Sand, med to coarse and med to coarse gravel				57	60	Shale, red			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG																																				
02	2	Soil, sandy																																							
2	10	Sand, med to coarse and med gravel, loose																																							
10	40	Sand, fine to coarse and fine to med gravel, loose with some silty spots																																							
40	57	Sand, med to coarse and med to coarse gravel																																							
57	60	Shale, red																																							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 30 Sept 82 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 325 This Water Well Record was completed on (mo/day/yr) 20 Jan 83 under the business name of Central Well & Pump Inc. by (signature) <i>[Signature]</i> INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.																																									