

Form WWC-5

KSA 82a-1212 Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Irrigation

WELL AND PUMP SERVICE

PO Box 268
Holdrege, NE 68949

825 Brewster Road

Phone: (308) 995-6143
1-800-860-2946

TEST HOLE LOG

CUSTOMER: Wichita, KS	
WELL ID: OB55S	
LOCATION: SE ¼ SE ¼ SW ¼ SE ¼, 5-T25S-R2W, Sedgewick Co., KS	
LATITUDE: 37° 53' 53.8"	
LONGITUDE: -97° 33' 37.1"	
FOOTAGES: 205' from the North section line and 1413 feet from the East section line.	
DATE: 10/26/09	DRILLED BY: Kyle Schoff, Doug Rezac, Cody Hanson

SWL:

PWL:

GPM:

from feet - to feet

0	5	Top soil and soft sandy clay
5	10	Sandy clay and traces of coarse sand to fine gravel
10	20	Sandy clay and coarse sand to medium gravel
20	30	Coarse sand to medium gravel

Well Information:

Well depth: 30'
Plain casing: 20'
Perf. Set: 20-30'

Bore hole: 6"
Perf. casing: 10'
Gravel: 15-30'

Casing size: 2"
Slot size: .020"
Grout: 0-15'