


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Comanche	Fraction CSW 1/4	1/4	1/4	Section number 30	Township number T 31	Range number S R 18	EW		
2. Distance and direction from nearest town or city: 2 miles No. of Coldwater Street address of well location if in city:					3. Owner of well: Yost Farms, Inc. R.R. or street: Coldwater, Kansas City, state, zip code: Well No. 5 (TH1-75)						
4. Locate with "X" in section below: Sketch map: 					6. Bore hole dia. 30 in. Completion date 1/22/76 Well depth 264 ft.						
5. Type and color of material					From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary				
					Sandy soil		0	2	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
					Med. to co. sand w/some clay		2	47	9. Casing: Material Stl Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 36.91 lbs./ft. Dia. 16 in. to 192 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219		
					Clay		47	57	10. Screen: Manufacturer's name Doerr Metal Type Steel Dia. 16" Slot/gauze 1/8 Length 72' Set between 170 ft. and 182 ft. 204 ft. and 264 ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/2 x 3/8		
					Med. to coarse sand & gravel		57	84	11. Static water level: <input type="checkbox"/> mo./day/yr. 43.8 ft. below land surface Date 3-25-76		
					Clay		84	100	12. Pumping level below land surfaces: 100.1 ft. after 3.5 hrs. pumping 1002 g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 1500 g.p.m.		
					Med. to coarse sand & gravel		100	110	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>		
					Clay		110	116	14. Well head completion: <input type="checkbox"/> Pitless adapter 12 Inches above grade		
					Med. to coarse sand & gravel		116	145	15. Well grouted? yes With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.		
					Clay		145	167	16. Nearest source of possible contamination: ft. 19000 Direction South Type city Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
Med. to coarse sand & med. gravel w/ some clay		167	182	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne Model number 12KM HP 100 Volts <input type="checkbox"/> Length of drop pipe 180 ft. capacity 100 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other							
Red shale		182	206	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name License No. Address Wichita, Kansas Signed [Signature] Date 1/27/76 Authorized representative							
18. Elevation:		19. Remarks:			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name License No. Address Wichita, Kansas Signed [Signature] Date 1/27/76 Authorized representative						
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		(Use a second sheet if needed)									

T
R
E
S
E
C
1/4
1/4
1/4
1/4
CSW

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5