

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: Meade SW 1/4 SW 1/4 NW 1/4 23 T 31 S R 28 W

Distance and direction from nearest town or city street address of well if located within city?

2 WATER WELL OWNER: MEADE FEEDERS 355 Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box #: 10096 "18"ROAD  
 City, State, ZIP code: MEADE, KS 67864- Application Number: 34080

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 220 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 90 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 90 ft. below land surface measured on mo/day/yr  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 12.25 in. to 220 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 03 FEEDLOT  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 6 in. to 200 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 21  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 200 ft. to 220 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 220 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 4 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 09 FEEDYARD  
 Direction from well? N.E How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5	TAN CLAY			
5	70	WHITE CLAY			
70	88	05 SAND AND 17 GRAVEL			
88	105	TAN CLAY			
105	195	GREY CLAY			
195	218	05 SAND AND 17 GRAVEL			
218	220	GREY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 4 /5 /96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 04/13/96 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse