

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: MEADE | NW 1/4 NW 1/4 SW 1/4 | 9 | T 31 S | R 28 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 5 MILES NORTH AND 2 MILES WEST OF MEADE

2 WATER WELL OWNER: LARK HURLEY
 RR#, St. Address, Box #: BOX 100 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SULPHUR SPRINGS, AR 72768- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 335 ELEVATION:
 Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 143 ft. below land surface measured on mo/day/yr 01/10/91
 Pump test data: Well water was ft. after hours pumping gpm
 Estimated Yield 25 gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 10 in. to 335 ft., and in. to ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 335 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: MILL SLOT

SCREEN PERFORATED INTERVALS: From ft. to ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 335 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 2 ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? SOUTH How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	2	TOP SOIL /			
2	10	BROWN CLAY /			
10	23	SANDY CLAY / CALICHE /			
23	44	BROWN CLAY /			
44	74	SAND FINE-SML / SOME SANDY CLAY /			
74	84	BROWN CLAY / LIMEROCK /			
84	100	BROWN CLAY /			
100	115	CLAY / FEW HARD LEDGES /			
115	140	SAND FN-MD CRS/ CEMENTED LDGS / FEW CLAY STRK			
140	195	SAND FN-MD CRS/ SMALL GRAVEL / USED WATER /			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/10/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/14/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichsmuth*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: MEADE | NW 1/4 NW 1/4 SW 1/4 | 9 | T 31 S | R 28 W

2 WATER WELL OWNER: LARK HURLEY
RR#, St. Address, Box #: BOX 100 Board of Agriculture, Division of Water Resources
City, State, ZIP code: SULPHUR SPRINGS, AR 72768- Application Number:

FROM	TO	LITHOLOGIC LOG
195	236	BLUE CLAY /
236	238	YELLOW CLAY /
238	260	SAND FN-MD CRS/ FEW SMALL GRAVEL /
260	285	BLUE CLAY /
285	286	LIMEROCK / HARD
286	300	SAND FINE-MED / FEW COARSE FEW CLAY STRKS/
300	315	SAND FN-MD CRS/ SMALL GRAVEL / CLAY STREAKS /
315	333	SAND FN-MD CRS/ SML-MED GRAVEL/
333	360	BRN SANDY CLAY/ LIMEROCK /

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/10/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/14/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmann*