



*The  
Professionals*

# MINTER-WILSON DRILLING CO.

Irrigation  
and Domestic  
Water Systems  
Complete Installation  
and Repairing

INCORPORATED

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

Fry Family Farms  
Meade County  
11-9-06

Location: NW $\frac{1}{4}$  20-31-28 - North of Plains to J Road - 11 $\frac{1}{2}$  miles east,  
 $\frac{1}{2}$  mile south - 100 ft. south of well

Static Water Level - 180 ft.

## Test #2

0' to 1' - Top soil  
1' to 9' - Brown clay  
9' to 30' - Brown clay with white rock  
30' to 34' - Fine sand  
34' to 44' - Brown clay with white rock  
44' to 84' - Brown clay  
84' to 118' - Fine to medium sand & gravel  
118' to 131' - Brown clay  
131' to 236' - Fine to medium sand & fine gravel  
236' to 248' - Brown blue clay  
248' to 286' - Blue clay  
286' to 412' - Fine to medium sand & gravel  
412' to 420' - Fine to medium sand & gravel - small clay streaks  
420' to 446' - Brown sandy clay  
446' to 454' - Fine sand  
454' to 474' - Brown clay  
474' to 481' - Brown clay with brown rock 40% - tight  
481' to 488' - Brown yellow clay  
488' to 500' - Shale - hard pull down