

1 LOCATION OF WATER WELL: Fraction | Section Number | Township Number | Range Number  
 COUNTY: 060 MEADE | SW 1/4 NE 1/4 SE 1/4 | 02 | T 31 S | R 28 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM MEADE; APPX 6 MILES NORTH

2 WATER WELL OWNER: BRUCE CLARK  
 RR#, St. Address, Box # : 18148 H ROAD Board of Agriculture, Division of Water Resources  
 City, State, ZIP code : MEADE, KS 67864- Application Number: 5477

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 422 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 121 ft. below land surface measured on mo/day/yr 05/25/07  
 Pump testdata: Well water was 191 ft. after 4 hours pumping 1503 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 24 in. to 422 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 02 IRRIGATION  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 422 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 189 ft. to 249 ft., From 337 ft. to 417 ft.  
 From 286 ft. to 316 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 422 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? SOUTHWEST How many feet? 142

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	11	04 SANDY CLAY			
11	74	01 CLAY 20 LIMESTONE 05 SAND			
74	123	01 CLAY			
123	178	04 SANDY CLAY 05 SAND			
178	225	05 SAND 13 FINE GRAVEL			
225	234	04 SANDY CLAY 05 SAND			
234	249	05 SAND			
249	280	04 SANDY CLAY 05 SAND			
280	294	28 ROCK 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/22/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/22/07 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 060 MEADE	SW 1/4 NE 1/4 SE 1/4	02	T 31 S	R 28 W

2 WATER WELL OWNER: BRUCE CLARK  
 RR#, St. Address, Box # : 18148 H ROAD Board of Agriculture, Division of Water Resources  
 City, State, ZIP code : MEADE, KS 67864- Application Number: 5477

FROM	TO	LITHOLOGIC LOG
294	316	05 SAND 11 GRAVEL 01 CLAY
316	335	04 SANDY CLAY 05 SAND
335	363	05 SAND
363	375	04 SANDY CLAY 05 SAND
375	396	07 FINE SAND 08 MEDIUM SAND 01 CLAY
396	417	05 SAND 28 ROCK 01 CLAY
417	428	31 CALICHE 28 ROCK
428	440	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/22/07 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 145 This Water Well Record was completed on, (mo/day/yr) 06/22/07  
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

