

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 MEADE SW 1/4 SW 1/4 SE 1/4 12 T 31 S R 29 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM MONTEZUMA; 17 1/4 MILE SOUTH, 1/2 MILE EAST

2 WATER WELL OWNER: MARY BETH CLAWSON
 RR#, St. Address, Box #: RT 1 BOX 65F Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SATANTA, KS 67870-9705 Application Number: 9,411-D1

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	---	NW	---	NE	---
M	W	---	---	---	E
l		SW		SE	
e			X		

4 DEPTH OF COMPLETED WELL 530 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 188 ft. below land surface measured on mo/day/yr 03/11/00
 Pump testdata: Well water was 233 ft. after 4 hours pumping 1603 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 530 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 530 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .25
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 285 ft. to 395 ft., From 465 ft. to 475 ft.
 From 402 ft. to 422 ft., From 485 ft. to 525 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 530 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	12	04 SANDY CLAY 31 CALICHE			
12	21	04 SANDY CLAY 31 CALICHE			
21	40	01 CLAY 31 CALICHE			
40	47	04 SANDY CLAY 05 SAND			
47	53	05 SAND 13 FINE GRAVEL			
53	75	04 SANDY CLAY 01 CLAY			
75	96	05 SAND 11 GRAVEL 01 CLAY			
96	102	01 CLAY			
102	111	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/07/00 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/23/00 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 060 MEADE SW 1/4 SW 1/4 SE 1/4 12 T 31 S R 29 W

2 WATER WELL OWNER: MARY BETH CLAWSON
RR#, St. Address, Box # : RT 1 BOX 65F Board of Agriculture, Division of Water Resources
City, State, ZIP code : SATANTA, KS 67870-9705 Application Number: 9,411-D1

FROM	TO	LITHOLOGIC LOG
111	133	05 SAND
133	145	04 SANDY CLAY 20 LIMESTONE
145	196	05 SAND 13 FINE GRAVEL
196	204	01 CLAY
204	220	04 SANDY CLAY 05 SAND
220	232	01 CLAY 05 SAND
232	240	07 FINE SAND 08 MEDIUM SAND 01 CLAY
240	256	01 CLAY 05 SAND
256	270	07 FINE SAND 08 MEDIUM SAND
270	285	01 CLAY
285	305	05 SAND 01 CLAY
305	317	05 SAND 01 CLAY
317	340	05 SAND 01 CLAY
340	393	05 SAND 13 FINE GRAVEL 01 CLAY
393	402	04 SANDY CLAY 20 LIMESTONE
402	422	04 SANDY CLAY 05 SAND 20 LIMESTONE
422	446	04 SANDY CLAY 20 LIMESTONE
446	464	04 SANDY CLAY 01 CLAY 20 LIMESTONE
464	475	01 CLAY 06 VERY FN SAND 07 FINE SAND
475	484	01 CLAY
484	499	01 CLAY 07 FINE SAND
499	510	01 CLAY 05 SAND 20 LIMESTONE
510	525	01 CLAY 28 ROCK
525	533	01 CLAY
533	550	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/07/00 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/23/00 under the business name of HENKLE DRILLING & SUPPLY

by (signature) *Bruce J. Reichmuth*