

The
Professionals

MINTER-WILSON DRILLING CO.
INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

Chester Rexford
Meade County
10-24-75

Location: NE 2-31-30
From Chester's House, 5 miles South, 2 miles West,
½ mile North, 40 rods West.

Static Water Level: 140

0	3	Top Soil
3	15	Brown Clay
15	22	Brown Sandy Clay
22	65	Fine Sand, Streaks of white Rock (10%) (Hard)
65	93	Brown Sandy Clay
93	110	Fine to Med. Sand & Gravel (Loose)
110	122	Fine to Med. Sand, Streaks of Clay (10%)
122	141	Fine to Med. Sand & Gravel (Loose)
141	200	Fine to Med. Sand & Gravel, Streaks of Clay (10%)
200	223	Fine to Med. Sand & Gravel, (Loose)
223	230	Fine to Med. Sand & Gravel, Streaks of Clay (10%)
230	312	Fine to Med. Sand & Gravel, (Loose)
312	320	Fine to Med. Sand & Gravel, Streaks of Clay (10%)
320	380	Fine to Med. Sand & Gravel, (Loose)
380	391	Brown & white Clay, Streaks Fine to Med. Sand & Gravel (Tight)
391	400	Fine to Med. Sand & Gravel
400	411	Fine to Med. Sand & gravel, Streaks of Clay (20%) (Tight)
411	421	Brown & White Sandy Clay
421	425	Fine to Med. Sand & Gravel
425	440	Brown Sandy Clay (Tight)

TD 400'