

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 MEADE SE 1/4 SE 1/4 NW 1/4 09 T 31 S R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 6.5 MILES NORTH OF PLAINS.

2 WATER WELL OWNER: MARY CLAWSON Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: RT. 1, BOX 65F
 City, State, ZIP code: SATAMTA, KS 67870- Application Number: 40,280

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 511 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 192 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 192 ft. below land surface measured on mo/day/yr 02/18/92
 Pump test data: Well water was 390 ft. after 4 hours pumping 1018 gpm
 Estimated Yield 0 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 30 in. to 516 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 219 ft., Dia 20 in. to 405 ft., Dia 16 in. to 511 ft.
 Casing height above land surface 12 in., weight 53 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT
 SCREEN PERFORATED INTERVALS: From 220 ft. to 260 ft., From 334 ft. to 344 ft.
 From 305 ft. to 315 ft., From 355 ft. to 385 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 511 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0'

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	14	04 SANDY CLAY 20 LIMESTONE			
14	65	31 CALICHE			
65	74	07 FINE SAND 01 CLAY			
74	83	04 SANDY CLAY			
83	90	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
90	98	01 CLAY			
98	108	05 SAND			
108	115	01 CLAY 05 SAND			
115	125	05 SAND 23 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/14/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/21/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas B. Henkle*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 060 MEADE	SE 1/4 SE 1/4 NW 1/4	09	T 31 S	R 30 W

2 WATER WELL OWNER: MARY CLAWSON
 RR#, St. Address, Box #: RT. 1, BOX 65F Board of Agriculture, Division of Water Resources
 City, State, ZIP code : SATAMTA, KS 67870- Application Number: 40,280

SCREEN PERFORATED INTERVALS: From 395 ft. to 405 ft., From 461 ft. to 511 ft.
 From 411 ft. to 441 ft., From 0 ft. to 0 ft.

FROM	TO	LITHOLOGIC LOG
125	136	04 SANDY CLAY 05 SAND
136	149	05 SAND 13 FINE GRAVEL 01 CLAY
149	191	01 CLAY
191	240	05 SAND 20 LIMESTONE
240	257	08 MEDIUM SAND 01 CLAY 20 LIMESTONE
257	305	01 CLAY 05 SAND
305	312	05 SAND 12 V. FINE GRAV
312	333	01 CLAY
333	345	05 SAND 13 FINE GRAVEL
345	354	01 CLAY 05 SAND
354	360	05 SAND 13 FINE GRAVEL
360	366	01 CLAY
366	377	07 FINE SAND 08 MEDIUM SAND
377	386	05 SAND 13 FINE GRAVEL
386	396	01 CLAY
396	405	07 FINE SAND 08 MEDIUM SAND 01 CLAY
405	412	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND
412	441	20 LIMESTONE 07 FINE SAND 04 SANDY CLAY
441	460	04 SANDY CLAY 07 FINE SAND
460	485	06 VERY FN SAND 07 FINE SAND 04 SANDY CLAY
485	497	05 SAND 13 FINE GRAVEL
497	508	05 SAND 13 FINE GRAVEL
508	512	04 SANDY CLAY 19 SHALE
512	520	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/14/92 and this record is true to the best of my knowledge and belief, Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/21/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas A. Henkle*