

WATER WELL RECORD Form WWC-5 KSA B2a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 MEADE SW 1/4 SW 1/4 SW 1/4 17 T 31 S R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 5.0 MILES NORTH AND 1.0 MILE WEST OF PLAINS

2 WATER WELL OWNER: KIRBY CLAWSON
 RR#, St. Address, Box #: RT. 1, BOX 65F Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SATANTA, KS 67870- Application Number: 6,749

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 463 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 215 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 215 ft. below land surface measured on mo/day/yr 02/15/92
 Pump test data: Well water was 263 ft. after 4 hours pumping 1582 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 30 in. to 463 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 228 ft., Dia 20 in. to 365 ft., Dia 16 in. to 463 ft.
 Casing height above land surface 12 in., weight 53 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 229 ft. to 269 ft., From 314 ft. to 344 ft.
 From 270 ft. to 290 ft., From 345 ft. to 365 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 463 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTH How many feet? 1154

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	10	04 SANDY CLAY			
10	42	01 CLAY 31 CALICHE			
42	59	04 SANDY CLAY 07 FINE SAND			
59	67	07 FINE SAND 08 MEDIUM SAND			
67	82	23 SANDSTONE 05 SAND			
82	105	05 SAND 11 GRAVEL			
105	109	01 CLAY			
109	153	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
153	175	01 CLAY 25 DOLOMITE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 02/12/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/21/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) Douglas A. Henkle

(Continued)

WATER WELL RECORD Form WWC-5 KSA B2a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 060 MEADE	SW 1/4 SW 1/4 SW 1/4	17	T 31 S	R 30 W

2 WATER WELL OWNER: KIRBY CLAWSON
 RR#, St. Address, Box # : RT. 1, BOX 65F Board of Agriculture, Division of Water Resources
 City, State, ZIP code : SATANTA, KS 67870- Application Number: 6,749

SCREEN PERFORATED INTERVALS: From 430 ft. to 460 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

FROM	TO	LITHOLOGIC LOG
175	190	05 SAND
190	205	01 CLAY
205	280	05 SAND 01 CLAY
280	290	07 FINE SAND 08 MEDIUM SAND
290	310	01 CLAY
310	315	04 SANDY CLAY 05 SAND
315	365	05 SAND 13 FINE GRAVEL
365	389	04 SANDY CLAY 20 LIMESTONE
389	432	01 CLAY 20 LIMESTONE
432	440	07 FINE SAND
440	460	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND
460	464	19 SHALE 20 LIMESTONE
464	480	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/12/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/21/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas B. Henkle*