

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 060 MEADE | SW 1/4 NW 1/4 SE 1/4 | 23 | T 31 S | R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3 NORTH, 1 EAST & 1 1/2 MILES NORTH OF PLAINS

2 WATER WELL OWNER: EDNA COLLINGWOOD TRUST
 RR#, St. Address, Box #: P.O. BOX 1184 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUTCHINSON, KS 67501-1184 Application Number: 27,426

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 464 | ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 194 ft. below land surface measured on mo/day/yr 05/11/95
 Pump test data: Well water was 364 ft. after 4 hours pumping 1200 gpm

Estimated Yield 1200 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 464 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 464 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 220 ft. to 240 ft., From 337 ft. to 407 ft.
 From 265 ft. to 315 ft., From 421 ft. to 461 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 464 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTH How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	25	01 CLAY			
25	80	04 SANDY CLAY 31 CALICHE			
80	107	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
107	108	20 LIMESTONE			
108	125	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
125	130	01 CLAY			
130	140	05 SAND 01 CLAY			
140	150	01 CLAY 20 LIMESTONE 31 CALICHE			
150	172	05 SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/04/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/18/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 060 MEADE | SW 1/4 NW 1/4 SE 1/4 | 23 | T 31 S | R 30 W

2 WATER WELL OWNER: EDNA COLLINGWOOD TRUST
RR#, St. Address, Box #: P.O. BOX 1184 Board of Agriculture, Division of Water Resources
City, State, ZIP code: HUTCHINSON, KS 67501-1184 Application Number: 27,426

FROM	TO	LITHOLOGIC LOG
172	179	01 CLAY
179	197	05 SAND 13 FINE GRAVEL
197	201	01 CLAY
201	235	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
235	251	01 CLAY 04 SANDY CLAY
251	260	01 CLAY 28 ROCK
260	315	05 SAND 01 CLAY 28 ROCK
315	335	01 CLAY
335	347	04 SANDY CLAY 20 LIMESTONE 05 SAND
347	362	04 SANDY CLAY 17 SAND & GRAVL
362	409	04 SANDY CLAY 20 LIMESTONE 05 SAND
409	423	01 CLAY 20 LIMESTONE 05 SAND
423	461	05 SAND 04 SANDY CLAY
461	470	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/04/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/18/95 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichmuth*