

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 088 SEWARD | SE 1/4 SE 1/4 SW 1/4 | 03 | T 31 S | R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM KISMET; APPX 11 1/2 MILES NORTH & 1/2 MILE EAST

2 WATER WELL OWNER: CLAWSON LAND PARTNERSHIP
 RR#, St. Address, Box #: PO BOX 279 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: PLAINS, KS 67869-0279 Application Number: 9691

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 524 | ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 266 ft. below land surface measured on mo/day/yr 07/10/06
 Pump test data: Well water was 332 ft. after 4 hours pumping 1073 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 524 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 524 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 298 ft. to 328 ft., From 449 ft. to 519 ft.
 From 360 ft. to 420 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 524 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTHEAST How many feet? 61

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	46	04 SANDY CLAY 07 FINE SAND			
46	67	01 CLAY			
67	84	04 SANDY CLAY 20 LIMESTONE			
84	93	07 FINE SAND 08 MEDIUM SAND			
93	126	04 SANDY CLAY			
126	150	05 SAND 13 FINE GRAVEL			
150	167	04 SANDY CLAY			
167	187	05 SAND 13 FINE GRAVEL			
187	192	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/07/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/16/06 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 088 SEWARD	SE 1/4 SE 1/4 SW 1/4	03	T 31 S	R 31 W

2 WATER WELL OWNER: **CLAWSON LAND PARTNERSHIP**
 RR#, St. Address, Box # : **PO BOX 279**
 City, State, ZIP code : **PLAINS, KS 67869-0279**

Board of Agriculture, Division of Water Resources
 Application Number: **9691**

FROM	TO	LITHOLOGIC LOG
192	230	05 SAND
230	237	05 SAND 01 CLAY
237	265	05 SAND 13 FINE GRAVEL
265	267	04 SANDY CLAY
267	277	05 SAND
277	297	04 SANDY CLAY 05 SAND
297	305	05 SAND
305	307	04 SANDY CLAY
307	328	05 SAND
328	364	01 CLAY
364	375	05 SAND 01 CLAY
375	397	04 SANDY CLAY 05 SAND
397	407	07 FINE SAND 08 MEDIUM SAND
407	420	04 SANDY CLAY 20 LIMESTONE
420	455	04 SANDY CLAY 05 SAND
455	468	07 FINE SAND 08 MEDIUM SAND
468	472	01 CLAY
472	489	05 SAND 28 ROCK
489	519	31 CALICHE 23 SANDSTONE
519	540	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) **07/07/06** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **145** This Water Well Record was completed on (mo/day/yr) **10/16/06** under the business name of **HENKLE DRILLING & SUPPLY** by (signature) *Bruce J. Reichert*