

1 LOCATION OF WATER WELL: Fraction **(NW SW)** Section Number Township Number Range Number
 COUNTY: **088 SEWARD** LOT 3 31 T 31 S R 31 W

Distance and direction from nearest town or city street address of well if located within city?

FROM KISMET; APPX 6 1/2 MILES NORTH & 2 MILES WEST

2 WATER WELL OWNER: **RICHARD BECK**
 RR#, St. Address, Box #: **10300 BADGLEY** Board of Agriculture, Division of Water Resources
 City, State, ZIP code: **ST LOUIS, KS 63126-** Application Number: **11087**

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL **533** ELEVATION: **0**
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL **278** ft. below land surface measured on mo/day/yr **11/20/06**
 Pump test data: Well water was **331** ft. after **4** hours pumping **1073** gpm
 Estimated Yield **0** gpm: Well water was **0** ft. after **0** hours pumping **0** gpm
 Bore Hole Diameter **24** in. to **533** ft., and in. to **0** ft.
 WELL WATER TO BE USED AS: **02 IRRIGATION**
 Was a chemical/bacteriological sample submitted to department? **No** ;
 If yes, mo/day/yr sample was submitted Water well disinfected? **Yes**

5 TYPE OF BLANK CASING USED: **01 STEEL** CASING JOINTS: **WELDED**
 Blank casing diameter **16** in. to **533** ft., Dia in. to **0** ft., Dia in. to **0** ft.
 Casing height above land surface **12** in., weight **42** lbs/ft. Wall thickness or gauge No. **.250**
 TYPE OF SCREEN OR PERFORATION MATERIAL: **01 STEEL**
 SCREEN OR PERFORATION OPENINGS ARE: **01 CONT. SLOT**

SCREEN PERFORATED INTERVALS: From **308** ft. to **398** ft., From **0** ft. to **0** ft.
 From **438** ft. to **528** ft., From **0** ft. to **0** ft.
 GRAVEL PACK INTERVALS: From **20** ft. to **533** ft., From **0** ft. to **0** ft.
 From **0** ft. to **0** ft., From **0** ft. to **0** ft.

6 GROUT MATERIAL **03 BENTONITE**
 Grout Intervals: From **0** ft. to **20** ft., From **0** ft. to **0** ft., From **0** ft. to **0** ft.
 What is the nearest source of possible contamination: **14 ABAND. WELL**
 Direction from well? **SOUTHWEST** How many feet? **101**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	75	04 SANDY CLAY			
75	126	05 SAND 11 GRAVEL			
126	128	04 SANDY CLAY			
128	144	05 SAND 13 FINE GRAVEL			
144	187	01 CLAY 05 SAND			
187	217	05 SAND 13 FINE GRAVEL			
217	225	04 SANDY CLAY			
225	256	05 SAND 13 FINE GRAVEL			
256	268	04 SANDY CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) **11/16/06** and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. **145** This Water Well Record was completed on (mo/day/yr) **12/22/06**
 under the business name of **HENKLE DRILLING & SUPPLY** by (signature)

1 LOCATION OF WATER WELL:	Fraction	(Nw Sw)	Section Number	Township Number	Range Number
COUNTY: 088 SEWARD	LOT 3		31	T 31 S	R 31 W

2 WATER WELL OWNER: RICHARD BECK

RR#, St. Address, Box # : 10300 BADGLEY

City, State, ZIP code : ST LOUIS, KS 63126-

Board of Agriculture, Division of Water Resources

Application Number: 11087

FROM	TO	LITHOLOGIC LOG
268	306	05 SAND 01 CLAY
306	355	05 SAND 13 FINE GRAVEL
355	368	07 FINE SAND 08 MEDIUM SAND 01 CLAY
368	400	05 SAND 01 CLAY
400	437	04 SANDY CLAY 05 SAND
437	464	05 SAND 01 CLAY
464	528	23 SANDSTONE 31 CALICHE 28 ROCK
528	540	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/16/06 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 12/22/06

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

