

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 088 SEWARD NE 1/4 NE 1/4 NW 1/4 16 T 31 S R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 6 MILES NORTH AND 5 1/2 MILES WEST OF PLAINS

2 WATER WELL OWNER: MRS. EMERY BALL
 RR#, St. Address, Box #: RT. 1, BOX 20 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: PLAINS, KS 67869- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 347 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 240 ft. below land surface measured on mo/day/yr 06/08/94
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 347 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 347 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 287 ft. to 347 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 347 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	11	04 SANDY CLAY			
11	19	07 FINE SAND 04 SANDY CLAY			
19	35	04 SANDY CLAY 01 CLAY 07 FINE SAND			
35	45	07 FINE SAND 04 SANDY CLAY			
45	50	20 LIMESTONE 01 CLAY			
50	78	01 CLAY			
78	82	07 FINE SAND 09 COARSE SAND 11 GRAVEL			
82	86	01 CLAY 07 FINE SAND			
86	149	07 FINE SAND 09 COARSE SAND 11 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/08/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/22/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 088 SEWARD : NE 1/4 NE 1/4 NW 1/4 : 16 : T 31 : R 31 W

2 WATER WELL OWNER: MRS. EMERY BALL
RR#, St. Address, Box #: RT. 1, BOX 20 Board of Agriculture, Division of Water Resources
City, State, ZIP code : PLAINS, KS 67869- Application Number:

FROM	TO	LITHOLOGIC LOG
149	154	01 CLAY 04 SANDY CLAY 07 FINE SAND
154	261	07 FINE SAND 09 COARSE SAND 01 CLAY
261	291	07 FINE SAND 09 COARSE SAND 11 GRAVEL
291	342	07 FINE SAND 09 COARSE SAND 01 CLAY
342	367	05 SAND 01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/08/94 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/22/94
under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce J. Reichmuth