

WINTER-WILSON DRILLING CO.

INCORPORATED

1001 E. 10TH AVE. • P.O. BOX 44 • GARDEN CITY, KANSAS 67841

V. M. ELLIS
SEWARD COUNTY
2/19/81

Location: NW 19-31-31 - Approx. $\frac{1}{2}$ mile west of existing well
Static Water Level - 235'

Test #

0	1	Top Soil
1	50	Brown Clay
50	63	Fine to Med. Sand & Gravel (Loose)
63	103	Brown Clay
103	269	Fine to Med. Sand & Gravel (Loose)
269	276	Brown & Gray Clay
276	360	Fine to Med. Sand & Gravel 10% Clay (Loose)
360	365	Brown & Gray Clay
365	388	Blue Clay
388	405	Fine to Med. Sand & Gravel 10% Clay (Loose)
405	410	Brown Clay
410	420	Fine to Med. Sand & Gravel 10% Clay (Loose) (Small Hard Streaks of White Rock)
420	465	Brown Clay & White Rock (Tight) (Hard Streaks)
465	488	Brown & Gray Clay (Tight) (Hard Streaks)
488	500	Brown Gray & Yellow Clay (Hard)

T.D. 425'