

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 088 SEWARD NE 1/4 NW 1/4 SW 1/4 21 T 31 S R 32 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM SUBLETTE; APPX 9 MILES SOUTH & 1 MILE EAST

2 WATER WELL OWNER: JESSE THOMAS  
 RR#, St. Address, Box #: RR 1 BOX 48 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: KISMET, KS 67859-9751 Application Number: 3504

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \		NW		NE	
1					
M					
i					
l					
e					
\ /					

4 DEPTH OF COMPLETED WELL 550 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 271 ft. below land surface measured on mo/day/yr 04/25/06  
 Pump test data: Well water was 300 ft. after 4 hours pumping 1617 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 550 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 550 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 316 ft. to 396 ft., From 485 ft. to 545 ft.  
 From 455 ft. to 465 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 550 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? SOUTH How many feet? 161

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	15	04 SANDY CLAY 31 CALICHE			
15	40	01 CLAY 31 CALICHE			
40	71	05 SAND 01 CLAY			
71	91	05 SAND			
91	97	01 CLAY 20 LIMESTONE			
97	101	01 CLAY			
101	280	05 SAND 13 FINE GRAVEL 01 CLAY			
280	330	05 SAND 13 FINE GRAVEL			
330	355	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/20/06 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06  
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: COUNTY: 088 SEWARD	Fraction NE 1/4 NW 1/4 SW 1/4	Section Number 21	Township Number T 31 S	Range Number R 32 W
---	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: JESSE THOMAS  
 RR#, St. Address, Box #: RR 1 BOX 48  
 City, State, ZIP code: KISMET, KS 67859-9751  
 Board of Agriculture, Division of Water Resources  
 Application Number: 3504

FROM	TO	LITHOLOGIC LOG
355	396	05 SAND 01 CLAY 13 FINE GRAVEL
396	455	01 CLAY 20 LIMESTONE 05 SAND
455	465	07 FINE SAND 01 CLAY
465	484	01 CLAY 05 SAND
484	503	23 SANDSTONE
503	525	23 SANDSTONE 31 CALICHE
525	545	23 SANDSTONE 31 CALICHE
545	550	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/20/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruno Reichert*