

DRILLERS TEST LOG

CUSTOMER'S NAME: Anderson Farms C/O Emprise Bank DATE: 11/14/89
 STREET ADDRESS: P. O. Box 595 TEST # 1 E. LOG Yes
 CITY & STATE: Garden City, Ks. 67846 DRILLER Shelden
 COUNTY Seward QUARTER SE SECTION 28 TOWNSHIP 31 RANGE 32

LOCATION 280' North of the old well & 20' East of undergroundline.

WELL LOCATION

Z	FOOTAGE			DESCRIPTION OF STRATA	STATIC WATER LEVEL:	
	From	Pay	TO		Proposed Well Depth:	
	0		2	Top soil.		
	2		27	Brown sandy & fine sand streaks & some small streaks of Caliche.		
	27		56	Sand fine to small.		
	56		102	Brown sandy clay & some small sand streaks & limerock.		
	102		230	Sand fine to medium coarse. Small to some medium gravel w/couple small clay streaks.		
70	230	53	283	Sand fine to medium coarse. Small to some medium gravel. Cemented from 262' to 264' & from 280' to 283'.		
	283		287	Brown sandy clay.		
70	287	107	394	Sand fine to medium coarse. Small to some medium gravel w/small clay streak at 373'.		
55	394	12	406	Sand & streaks of white rock w/some brown sandy clay streaks.		
	406		450	Brown clay "Sluffes" w/lots fine sand streaks.		
60	450	28	478	Sand fine to medium coarse. Small brown & white rock.		
	478		485	Brown sandy clay.		
25	485	37	522	Sandstone . Yellow in color. Drills loose in places, from 502' to 521'.		
	522		524	Gray soapstone.		
	524		542	Red bed.		
				Total Depth = 542' 481'		
				1 - 50# Bag Q-Gel		
				1 - Perma plug		
				1 - 50# Bag Hole plug		
				Set up North		
				Pit on East		

GARDEN CITY, KS 67846
 3795 West Jones Ave.

HENKLE DRILLING & SUPPLY CO., INC.
 IRRIGATION HEADQUARTERS

316-277-2389

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * * STOCK WELLS