

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 088 SEWARD NE 1/4 NE 1/4 NE 1/4 18 T 31 S R 32 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 8 1/4 MILES SOUTH OF SUBLETTE

2 WATER WELL OWNER: MRS. HAROLD LOWER  
 RR#, St. Address, Box #: HCR 1 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: SUBLETTE, KS 67877- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 425 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 260 ft. below land surface measured on mo/day/yr 09/14/94  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 11 in. to 425 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 425 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 365 ft. to 425 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 425 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	15	01 CLAY			
15	63	01 CLAY 04 SANDY CLAY			
63	66	04 SANDY CLAY			
66	71	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
71	82	04 SANDY CLAY			
82	86	07 FINE SAND 09 COARSE SAND 15 CRS GRAVEL			
86	97	04 SANDY CLAY			
97	152	07 FINE SAND 09 COARSE SAND 15 CRS GRAVEL			
152	155	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/14/94 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/03/94  
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number  
COUNTY: 088 SEWARD : NE 1/4 NE 1/4 NE 1/4 : 18 : T 31 S : R 32 W

2 WATER WELL OWNER: MRS. HAROLD LOWER  
RR#, St. Address, Box # : HCR 1 Board of Agriculture, Division of Water Resources  
City, State, ZIP code : SUBLETTE, KS 67877- Application Number:

FROM	TO	LITHOLOGIC LOG
155	170	07 FINE SAND 08 MEDIUM SAND 15 CRS GRAVEL
170	175	01 CLAY 07 FINE SAND
175	182	20 LIMESTONE 01 CLAY
182	330	07 FINE SAND 09 COARSE SAND 01 CLAY
330	336	20 LIMESTONE 05 SAND
336	353	04 SANDY CLAY 01 CLAY
353	358	19 SHALE 01 CLAY
358	368	07 FINE SAND 10 V CRS SAND 01 CLAY
368	425	07 FINE SAND 09 COARSE SAND 01 CLAY
425	457	04 SANDY CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was  
completed on (mo/day/year) 09/14/94 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/03/94  
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*