

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
COUNTY: 088 SEWARD		SW 1/4 NW 1/4 NE 1/4		01		T 31 S		R 32 W	
Distance and direction from nearest town or city street address of well if located within city?									
APPROX. 3 MILES EAST & 6 1/4 MILES SOUTH OF SUBLETTE									
2 WATER WELL OWNER:		BIRD, RANDALL							
RR#, St. Address, Box # :		HCR 1 BOX 81				Board of Agriculture, Division of Water Resources			
City, State, ZIP code :		SUBLETTE, KS 67877-				Application Number: 10,797			
3 LOCATE WELL'S LOCATION WITH		4 DEPTH OF COMPLETED WELL		511		ELEVATION:		0	
AN "X" IN SECTION BOX:		Depth(s) Groundwater Encountered		1.		0 ft.		2. 0 ft. 3. 0 ft.	
/ \		WELL'S STATIC WATER LEVEL 265 ft. below land surface measured on mo/day/yr 04/22/95							
1		Pump test data: Well water was 446 ft. after 4 hours pumping 700 gpm							
NW X NE		Estimated Yield 700 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm							
M		Bore Hole Diameter 24 in. to 511 ft., and in. to 0 ft.							
W		WELL WATER TO BE USED AS: 02 IRRIGATION							
E		Was a chemical/bacteriological sample submitted to department? No ;							
e		If yes, mo/day/yr sample was submitted Water well disinfected? Yes							
/ \									
5 TYPE OF BLANK CASING USED: 01 STEEL		CASING JOINTS: WELDED							
Blank casing diameter 16 in. to 511 ft., Dia		in. to 0 ft., Dia in. to 0 ft.							
Casing height above land surface 12 in., weight		42 lbs/ft. Wall thickness or gauge No. .250							
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL									
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT									
SCREEN PERFORATED INTERVALS:		From 290 ft. to 330 ft., From 453 ft. to 473 ft.							
		From 351 ft. to 391 ft., From 491 ft. to 511 ft.							
GRAVEL PACK INTERVALS:		From 20 ft. to 511 ft., From 0 ft. to 0 ft.							
		From 0 ft. to 0 ft., From 0 ft. to 0 ft.							
6 GROUT MATERIAL 03 BENTONITE									
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.									
What is the nearest source of possible contamination: 14 ABAND. WELL									
Direction from well? SOUTH		How many feet? 295							
FROM	TO	LITHOLOGIC LOG				FROM	TO	PLUGGING INTERVALS	
0	1	02 SILT							
1	8	03 SILTY CLAY							
8	15	04 SANDY CLAY							
15	26	04 SANDY CLAY							
26	52	05 SAND 04 SANDY CLAY 31 CALICHE							
52	79	01 CLAY 04 SANDY CLAY							
79	132	05 SAND 13 FINE GRAVEL 14 MED GRAVEL							
132	139	04 SANDY CLAY							
139	162	06 VERY FN SAND 07 FINE SAND 08 MEDIUM SAND							
162	172	05 SAND 13 FINE GRAVEL 14 MED GRAVEL							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was									
completed on (mo/day/year) 04/18/95 and this record is true to the best of my knowledge and belief. Kansas									
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/19/95									
under the business name of HENKLE DRILLING & SUPPLY by (signature)									

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 088 SEWARD | SW 1/4 NW 1/4 NE 1/4 | 01 | T 31 S | R 32 W

2 WATER WELL OWNER: BIRD, RANDALL

RR#, St. Address, Box #: HCR 1 BOX 81

City, State, ZIP code: SUBLETTE, KS 67877-

Board of Agriculture, Division of Water Resources

Application Number: 10,797

FROM	TO	LITHOLOGIC LOG
172	182	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
182	197	04 SANDY CLAY 05 SAND
197	209	01 CLAY
209	222	04 SANDY CLAY 05 SAND
222	240	01 CLAY
240	289	05 SAND 01 CLAY
289	309	05 SAND 13 FINE GRAVEL
309	326	05 SAND 13 FINE GRAVEL
326	351	01 CLAY 04 SANDY CLAY 05 SAND
351	362	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL
362	384	05 SAND 04 SANDY CLAY
384	392	01 CLAY 05 SAND 01 CLAY
392	410	01 CLAY 20 LIMESTONE
410	423	04 SANDY CLAY 01 CLAY
423	472	01 CLAY
472	491	04 SANDY CLAY 01 CLAY
491	502	23 SANDSTONE
502	517	31 CALICHE 19 SHALE
517	520	19 SHALE

3 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/18/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/19/95 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce J. Reichmuth