

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 088 SEWARD SW 1/4 SW 1/4 SE 1/4 28 T 31 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?

FROM SUBLETTE, APPX 11 3/4 MILES SOUTH & 2 MILES WEST

2 WATER WELL OWNER: ED PITTMAN
 RR#, St. Address, Box #: RT 2 BOX 243 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: LIBERAL, KS 67901- Application Number: 740

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 535 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 250 ft. below land surface measured on mo/day/yr 08/06/07
 Pump test data: Well water was 281 ft. after 4 hours pumping 1458 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 535 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 535 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 430 ft. to 530 ft., From 0 ft. to 0 ft.
 From 310 ft. to 430 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 535 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTHWEST How many feet? 133

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	52	01 CLAY 31 CALICHE			
52	80	01 CLAY 05 SAND			
80	209	05 SAND 11 GRAVEL 28 ROCK			
209	240	05 SAND 13 FINE GRAVEL			
240	256	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
256	305	05 SAND 01 CLAY			
305	349	05 SAND 13 FINE GRAVEL			
349	366	05 SAND			
366	405	05 SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/02/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/27/07 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 088 SEWARD	SW 1/4 SW 1/4 SE 1/4	28	T 31 S	R 33 W

2 WATER WELL OWNER:	ED PITTMAN	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	RT 2 BOX 243	Application Number: 740
City, State, ZIP code :	LIBERAL, KS 67901-	

FROM	TO	LITHOLOGIC LOG
405	457	05 SAND
457	464	01 CLAY 20 LIMESTONE
464	490	23 SANDSTONE
490	500	31 CALICHE 23 SANDSTONE 19 SHALE
500	530	31 CALICHE 23 SANDSTONE
530	540	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/02/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/27/07 under the business name of HENKLE DRILLING & SUPPLY by (signature)

