

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 095 STEVENS SW 1/4 SW 1/4 NE 1/4 35 T 31 S R 35 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM MOSCOW; APPX 6 1/2 MILES SOUTH & 4 1/2 MILES EAST

2 WATER WELL OWNER: SCOTT YOUNG ESTATE
 RR#, St. Address, Box #: 502 SHOSHONE ST Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SATANTA, KS 67870- Application Number: 27,561

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \		NW		NE	
1	W	X		E	
M i l e		SW		SE	
\ /					

4 DEPTH OF COMPLETED WELL 542 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 320 ft. below land surface measured on mo/day/yr 06/16/06
 Pump test data: Well water was 351 ft. after 4 hours pumping 1396 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 542 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 542 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 368 ft. to 448 ft., From 0 ft. to 0 ft.
 From 477 ft. to 537 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 542 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHWEST How many feet? 158

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	75	01 CLAY 31 CALICHE 05 SAND			
75	143	01 CLAY			
143	157	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
157	176	01 CLAY			
176	205	05 SAND 13 FINE GRAVEL 01 CLAY			
205	248	05 SAND 01 CLAY			
248	267	01 CLAY 05 SAND			
267	306	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
306	324	01 CLAY 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/14/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: COUNTY: 095 STEVENS	Fraction SW 1/4 SW 1/4 NE 1/4	Section Number 35	Township Number T 31 S	Range Number R 35 W
--	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: SCOTT YOUNG ESTATE
 RR#, St. Address, Box # : 502 SHOSHONE ST
 City, State, ZIP code : SATANTA, KS 67870-

Board of Agriculture, Division of Water Resources
 Application Number: 27,561

FROM	TO	LITHOLOGIC LOG
324	347	01 CLAY 05 SAND
347	363	05 SAND 01 CLAY
363	398	05 SAND 01 CLAY
398	411	01 CLAY 20 LIMESTONE
411	418	07 FINE SAND 01 CLAY
418	448	05 SAND 01 CLAY
448	465	01 CLAY 20 LIMESTONE
465	479	01 CLAY 20 LIMESTONE 05 SAND
479	520	31 CALICHE 23 SANDSTONE 20 LIMESTONE
520	537	23 SANDSTONE 31 CALICHE
537	542	31 CALICHE 20 LIMESTONE
542	550	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/14/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

