

26-31S-35W
SW SW SE

Stearns Co
dupl.

31-35-26dec2 (Well No.) Sample _____ log of test hole _____ ~~suggested~~ drilled

by KGS for USGS

in SW SW SE sec. 26, T. 31 S., R. 35 W. 80 ft. east and 20 ft. north of
(Location)
Sk-cor. sec. 26 (38' east of pumped well)

Aug. 1966 (Date); depth to water, _____ feet;

altitude of land surface _____ feet.

	Thickness, feet	Depth, feet
Silt loam, brown	2	2
Silt loam, light brown; contains tan-white caliche nodules (CCA zone?)	2	4
Silt loam, tan-brown	8	12
Silt, clayey, limy, reddish-tan and tan-white	4	16
Silt, sandy, reddish-tan; interbedded with reddish-tan clayey silt	9	25
Silt, sandy, clayey, reddish-tan; contains limy silty clay layers	13	38
Silt, limy, clayey, tan-white	4	42
Clay, very sandy, reddish-tan; contains very fine to very coarse sand streaks	5	47
Clay, silty, sandy, reddish-tan	5	52
Silt, very sandy, slightly clayey, reddish-tan	10	62
Sand, very fine to very coarse and very fine to coarse gravel	8	70
Clay, tan; interbedded with red-tan sandy clayey silt	7	77
Clay, silty, red-tan	15	92
Clay, tight, silty, tan	5	97
Clay, sandy, silty, reddish-tan	8	105
Clay, sandy, silty, reddish tan; contains tan-white caliche nodules	20	125
Clay, very sandy, gravelly, silty, reddish-tan; contains tan-white caliche nodules	7	132
Sand, very fine to very coarse; contains 40% very fine to coarse gravel	10	142

~~31-35-26dec2~~ cont. Sample _____ log of test hole _____ augered drilled

in _____
(Location)

_____ ; depth to water, _____ feet;
(Date)

altitude of land surface _____ feet.

	Thickness, feet	Depth, feet
Sand, very fine to very coarse and very fine to medium gravel;		
contains tan sandy clay streaks	11	153
Clay, olive-tan to gray interbedded with tan very silty fine to medium		
sand streak	10	163
Clay, very sandy, gravelly, silty, reddish-tan; contains tan-white		
caliche streaks	12	175
Sand, very fine to coarse, and very fine to medium gravel; contains tan-		
white caliche and reddish-tan very sandy silt streaks	20	195
Sand, fine to very coarse, and 40% very fine to coarse gravel;		
drilled loose	15	210
Sand, fine to very coarse and 30% very fine to coarse gravel; contains		
tan very sandy silt streaks	4	214
Sand, fine to very coarse and 50% very fine to coarse gravel	9	223
Clay, sandy, olive-gray	2	225
Sand, fine to very coarse and 50% very fine to coarse gravel	38	263
Clay, sandy, silty, tan	5	268
Silt, very sandy, clayey, tan; contains tan-white caliche streaks	16	284
Sand, very fine to medium; contains tan very sandy clayey silt streaks	9	293
Sand, fine to coarse and very fine gravel; contains tan-white caliche		
streaks	12	305
Silt, very sand, tan	5	310