

DRILLERS TEST LOG

CUSTOMER'S NAME: W.T. & Larry Lightcap **DATE:** 5/25/89
STREET ADDRESS: 23 W. Seabrook Cove **TEST #** 1 **E. LOG** Yes
CITY & STATE: Newport Beach, Calif. 92660 **DRILLER** Wildeman
COUNTY Stevens **QUARTER** SE **SECTION** 28 **TOWNSHIP** 31 **RANGE** 37
LOCATION 280' West of the well or 1435' West of the SE Corner.

Z	FOOTAGE			DESCRIPTION OF STRATA	STATIC WATER LEVEL:
	From	Pay	TO		Proposed Well Depth:
	0		2	Top soil.	
	2		27	Sand fine to small, Caliche & Brown clay.	
	27		61	Brown clay.	
	61		86	Sand fine to medium coarse. Small to large gravel. (Drilled loose & rough in places).	
	86		100	Brown clay & limerock streaks.	
	100		119	Brown clay, Caliche & fine sand streaks.	
	119		127	Brown clay & limerock streaks.	
	127		140	Sand fine to medium coarse & few rock ledges.	
	140		143	Brown clay.	
	143		183	Sand fine to medium coarse. Small gravel & few clay streaks.	
	183		202	Brown clay, white clay & few sand streaks.	
40	202	18	220	Sand fine to medium coarse & few clay streaks (loose).	
50	220	21	241	Sand fine to medium coarse & few rock ledges (loose).	
60	241	22	263	Sand fine to medium coarse. Small brown gravel with few white & brown rock streaks & few ledges. (loose used water).	
55	263	13	275	Sand fine to medium coarse & few clay streaks.	
	275		380	Brown clay & limerock streaks (sticky)	
75	380	65	445	Sand fine to medium coarse. Small to medium brown gravel & brown rock (drilled loose & rough).	
	445		462	Brown clay.	
30	462	4	466	Fine sand.	
	466		476	Brown clay.	
65	476	8	484	Sand fine to medium coarse. Small brown gravel.	
	484		494	Clay.	
	494		500	Red bed.	
				WELL DEPTH = 487'	
				Gasline 70' South of test hole running East & West	
				JED "A"	
				Set up South	
				Pits on the West	
				3 - Sacks of Quick Gel	
				1 - Sack of Hole plug	
				1 - Perma plug	
				1 - Set of 4 3/4" Drag Blades	

GARDEN CITY, KS 67846
3795 West Jones Ave.

HENKLE DRILLING & SUPPLY CO., INC.

316-277-2389

IRRIGATION HEADQUARTERS

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * * STOCK WELLS