

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 095 STEVENS SE 1/4 SW 1/4 NE 1/4 29 T 31 S R 35 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3 1/4 MILES EAST OF MOSCOW

2 WATER WELL OWNER: BROLLIER EST %LORAN ZABEL
 RR#, St. Address, Box #: BOX 728 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUGOTON, KS 67951- Application Number: 6073 3424 8059

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 550 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 305 ft. below land surface measured on mo/day/yr 12/06/
 Pump test data: Well water was 418 ft. after 4 hours pumping 289 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 550 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 550 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 300 ft. to 410 ft., From 0 ft. to 0 ft.
 From 475 ft. to 545 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 550 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? 100 FT SOUTH AND 40 FT NORTH How many feet? 108

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 CLAY 02 SILT			
20	50	01 CLAY 07 FINE SAND 20 LIMESTONE			
50	120	01 CLAY			
120	134	01 CLAY 20 LIMESTONE			
134	165	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
165	185	01 CLAY			
185	190	05 SAND			
190	235	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
235	284	01 CLAY			
284	300	01 CLAY 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/17/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/11/93 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 095 STEVENS | SE 1/4 SW 1/4 NE 1/4 | 29 | T 31 S | R 35 W

2 WATER WELL OWNER: BROLLIER EST %LORAN ZABEL
 RR#, St. Address, Box #: BOX 728 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUGOTON, KS 67951- Application Number: 6073 3424 8059

FROM	TO	LITHOLOGIC LOG
300	313	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL
313	325	01 CLAY
325	367	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
367	375	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL
375	410	01 CLAY 07 FINE SAND 08 MEDIUM SAND
410	472	01 CLAY
472	503	07 FINE SAND 09 COARSE SAND 01 CLAY
503	547	23 SANDSTONE 31 CALICHE 20 LIMESTONE
547	560	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/17/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/11/93 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*