

DRILLERS TEST LOG

CUSTOMER'S NAME: Tom Lahey DATE: 2/9/90
 STREET ADDRESS: _____ TEST # 4 E. LOG Yes
 CITY & STATE: Moscow, Ks. 67952 DRILLER Shelden
 COUNTY Stevens QUARTER NE SECTION 9 TOWNSHIP 31 RANGE 36

LOCATION 60' Southeast of Test #1.

POSSIBLE WELL LOCATION

Z	FOOTAGE			DESCRIPTION OF STRATA	STATIC WATER LEVEL: <u>~150'</u>
	From	Pay	TO		Proposed Well Depth:
	0		2	Top soil.	
	2		61	Brown sandv clay & some caliche & some small sand streaks.	
	61		80	Brown sandv clay & lots limerock.	
	80		100	Sand fine to medium coarse. Small to large gravel. Cemented in places w/some clay streaks.	
	100		107	Brown sandv clay.	
	107		125	Sand fine to medium coarse. Cemented in places w/some clay streaks.	
	125		144	Brown sandy clay & some small sand streaks.	
55	144	<u>101</u>	258	Sand fine to medium coarse. Small brown & tan rock. Drilled loose in places.	
	258		270	Brown sandy clay & small sand streaks.	
55	270	5	275	Sand fine to medium coarse. Drilled loose.	
40	275	10	285	Sand fine to small w/clay streaks.	
55	285	47	332	Sand fine to medium coarse.	
	332		335	Brown clay.	
15	335	17	352	Sandstone & soapstone streaks.	
10	352	18	370	Soapstone & sandstone streaks.	
15	370	70	440	Sandstone.	
10	440	10	450	Soapstone & sandstone.	
15	450	10	460	Sandstone.	
10	460	10	470	Soapstone & sandstone streaks.	
15	470	14	484	Sandstone.	
	484		492	Red bed.	
				Well depth = 487'	
				1 - Perma plug	
				1 - bag Hole plug	
				1 - bag O-Gel	
				Set up West	
				Pit on North	

GARDEN CITY, KS 67846
 3795 West Jones Ave.

HENKLE DRILLING & SUPPLY CO., INC.

316-277-2389

IRRIGATION HEADQUARTERS

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * * STOCK WELLS