

The
Professionals

MINTER-WILSON DRILLING CO.
INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

Moscow Equity
Stevens County
6-2-87

Location: NW $\frac{1}{4}$ 24-31-36
From Moscow $\frac{1}{2}$ E., 1/8 N., $\frac{1}{2}$ E. &
approx. 40' NW of office

Static Water Level - 218

Test #1

0 3 Top soil
3 153 Brown clay
153 157 Fine to medium sand
157 172 Brown clay
172 182 Brown clay - 15% sand
182 197 Fine sand - loose
197 242 Brown clay - small sand strip
242 260 Fine to medium sand - loose
260 351 Fine to medium sand & gravel
351 359 Brown clay - sticky
359 364 Fine to medium sand & gravel
364 393 Brown sandy clay - Hard
393 412 Fine to medium sand - 10% clay
412 427 Fine to medium sand & gravel - brown yellow
rock mixed - 10% clay
427 470 Brown clay
470 500 Yellow clay

Well 428'
10-5/8" Hole
6-5/8" Steel Casing
359' Plain
10' Perf.
29' Plain
30' Perf.
2 Tons Gravel