

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 095 STEVENS SW 1/4 SE 1/4 SW 1/4 11 T 31 S R 37 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM MOSCOW; APPX 2 MILES NORTH & 5 MILES WEST

2 WATER WELL OWNER: ROME FARM PARTNERSHIP
 RR#, St. Address, Box #: HC 01 BOX 18 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUGOTON, KS 67951-9014 Application Number: 3,595

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \		NW		NE	
1	---	---	---	---	---
M	W	---	---	---	E
i	---	---	---	---	---
l	---	SW	---	SE	---
e	---	---	---	---	---
\ /	---	X	---	---	---

4 DEPTH OF COMPLETED WELL 504 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft. 0 ft.

WELL'S STATIC WATER LEVEL 261 ft. below land surface measured on mo/day/yr 05/30/06
 Pump test data: Well water was 284 ft. after 4 hours pumping 1547 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 504 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 504 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 299 ft. to 499 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 504 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 290

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	10	04 SANDY CLAY			
10	21	07 FINE SAND 04 SANDY CLAY			
21	90	04 SANDY CLAY 01 CLAY 05 SAND			
90	111	05 SAND 11 GRAVEL			
111	171	05 SAND 13 FINE GRAVEL 01 CLAY			
171	185	01 CLAY			
185	201	05 SAND			
201	205	01 CLAY			
205	230	05 SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/26/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: COUNTY: 095 STEVENS	Fraction SW 1/4 SW 1/4 SW 1/4	Section Number 11	Township Number T 31 S	Range Number R 37 W
--	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP code :	ROME FARM PARTNERSHIP HC 01 BOX 18 HUGOTON, KS 67951-9014	Board of Agriculture, Division of Water Resources Application Number: 3,595
---	---	--

FROM	TO	LITHOLOGIC LOG
230	237	01 CLAY 05 SAND
237	245	05 SAND 13 FINE GRAVEL
245	255	01 CLAY
255	287	05 SAND 11 GRAVEL
287	293	01 CLAY
293	337	05 SAND 28 ROCK
337	341	01 CLAY
341	434	05 SAND 28 ROCK
434	441	04 SANDY CLAY
441	458	05 SAND 28 ROCK
458	462	01 CLAY
462	499	23 SANDSTONE
499	510	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/26/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/08 under the business name of HENKLE DRILLING & SUPPLY by (signature) 