

DRILLERS TEST LOG

CUSTOMER'S NAME: Robert Parsons DATE: 7/28/88
 STREET ADDRESS: 1409 South Madison TEST # 1 E. LOG Yes
 CITY & STATE: Hugoton, Ks. 67951 DRILLER Shelden
 COUNTY Stevens QUARTER NW SECTION 9 TOWNSHIP 31 RANGE 37

LOCATION Approximately 1/4 mile North of the Old Well.

WELL LOCATION

%	FOOTAGE		TO	DESCRIPTION OF STRATA	STATIC WATER LEVEL: _____
	From	Pay			Proposed Well Depth:
	0		2	Top Soil.	
	2		33	Brown sandy clay.	
	33		45	Sand fine to medium.	
	45		110	Brown sandy clay & fine sand streaks & few Limerock ledges.	
	110		155	Sand fine to medium coarse with few clay streaks.	
	155		161	Brown sandy clay.	
	161		193	Sand fine to medium coarse. Cemented ledges. Used pull downs.	
	193		196	Brown sandy clay.	
60	196	26	222	Sand fine to medium coarse with few small gravel.	
65	222	21	243	Sand fine to medium coarse. Small to medium gravel.	
	243		270	Brown sandy clay & few sand streaks.	
60	270	13	283	Sand fine to medium coarse with Small brown gravel.	
60	283	44	327	Sand fine to medium coarse with few small gravel.	
65	327	23	350	Sand fine to medium coarse. Small to medium brown gravel.	
65	350	42	392	Sand fine to medium coarse. Small to large gravel. Used Water.	
	392		397	White Soapstone & Brown sandy clay.	
45	397	114	511	Sandstone & Soapstone streaks. Mix 1 sack O-Jel & 1 sack Bran. Used lots water.	
	511		519	Soapstone & Limestone ledges.	
	519		525	Red Bed.	
				Well Depth = 514'	
				Set up North	
				Pit on East	
				2 - 50# sacks - O-Jel	
				1 - 100# sack - Bran	
				1 - Dry Hole Plug	

GARDEN CITY, KS 67846 HENKLE DRILLING & SUPPLY CO., INC. 316-277-2389
 3795 West Jones Ave. IRRIGATION HEADQUARTERS

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * * STOCK WELLS