

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 095 STEVENS NW 1/4 NW 1/4 NW 1/4 11 T 31 S R 37 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 3 MILES NORTH AND 6 MILES WEST OF MOSCOW.

2 WATER WELL OWNER: PARSONS FARMS  
 RR#, St. Address, Box #: HCD 1, BOX 13 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: HUGOTON, KS 67951- Application Number: 125&18,776

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 498 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 240 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 240 ft. below land surface measured on mo/day/yr 08/02/91  
 Pump testdata: Well water was 273 ft. after 4 hours pumping 1576 gpm  
 Estimated Yield 1500 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 24 in. to 498 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 02 IRRIGATION  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 498 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 27 ft. to 33 ft., From 0 ft. to 0 ft.  
 From 358 ft. to 498 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 498 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? EAST How many feet? 190

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	39	04 SANDY CLAY 05 SAND			
39	77	01 CLAY			
77	98	08 MEDIUM SAND 14 MED GRAVEL 01 CLAY			
98	100	04 SANDY CLAY			
100	141	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
141	144	04 SANDY CLAY			
144	177	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
177	201	04 SANDY CLAY 05 SAND			
201	211	07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/31/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/15/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) Douglas R. Henkle

