

DRILLERS TEST LOG

CUSTOMERS NAME Morton Brewer DATE 2/19/79
 STREET ADDRESS _____ TEST # 1 E. LOG Yes
 CITY & STATE Hugoton, Kansas DRILLER Martinez
 COUNTY Stevens QUARTER SW SECTION 26 TOWNSHIP 31 RANGE 37

LOCATION _____

WELL LOCATION _____

%	FOOTAGE			DESCRIPTION OF STRATA	Static Water Level _____
	From	Pay	To		Proposed Well Depth _____
	0		2	Top Soil	
	2		63	Brown clay	
	63		76	Sand fine to med coarse with small to med size gravel.	
	76		123	Brown clay and limerock sts.	
	123		158	Sand fine to med coarse with a few ledges.	
	158		161	Brown clay	
50	161	07	187	Sand fine to med coarse and small gravel. Loose - used water.	
	187		198	Brown clay	
40	198	10	208	Sand fine to med. Loose - used some water.	
	208		241	Brown clay with a few limerock sts.	
60	241	19	260	Sand fine to med coarse, small brown gravel with a few white and brown rock sts and a few ledges. Loose - used water.	
30	260	08	268	Sand fine to med with a few clay sts. Loose - used used some water.	
	268		280	Brown clay with a few limerock sts.	
	280		307	White clay	
60	307	13	320	Sand fine to med coarse, small gravel with a few tan rock sts. Loose - used water.	
60	320	39	359	Sand fine to med coarse, small brown gravel with a few white and brown rock sts. Loose - used water.	
	359		365	Brown clay	
	365		385	Brown and white clay with a few limerock sts.	
	385		425	Brown clay	
50	425	07	432	Sand fine to med coarse. Loose - used water.	
	432		437	Brown clay	
60	437	52	489	Sand fine to med coarse and small brown gravel. A few white and brown rock sts. Loose - used water.	
Fair	489	26	515	Sandstone - drilled tight - used water.	
	515		520	Redbed	
			181		
TOTAL DEPTH OF WELL 518'					
Set up East					
Dig pit on the South					

GARDEN CITY, KS
Phone 276-3278

HENKLE DRILLING & SUPPLY CO., INC.
IRRIGATION HEADQUARTERS

SUBLETTE, KS
Phone 675-4311

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * STOCK WELLS