


1 LOCATION OF WATER WELL: Fraction $\frac{1}{4}$ C $\frac{1}{4}$ NW $\frac{1}{4}$ Section Number 36 Township Number T 31 S Range Number R 37W **EW**

Distance and direction from nearest town or city street address of well if located within city?

4 MILES SOUTHWEST MOSCOW, KS

2 WATER WELL OWNER: BEREXCO INC.
 RR#, St. Address, Box #: 100 N BROADWAY STE 970
 City, State, ZIP Code: WICHITA, KS 672022209

#1-36 ALBRIGHT TRUST
 Board of Agriculture, Division of Water Resources
 Application Number: 940505

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:  4 DEPTH OF COMPLETED WELL: 420 ft. ELEVATION: 420 ft.
 Depth(s) Groundwater Encountered 1. 200 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL .200 ft. below land surface measured on mo/day/yr 12-15-94
 Pump test data: Well water was .220 ft. after . . . hours pumping .100 gpm
 Est. Yield .100 gpm: Well water was . . . ft. after . . . hours pumping . . . gpm
 Bore Hole Diameter .11 in. to 420 ft., and . . . in. to . . . ft.
 WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well
 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)
 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well
 Was a chemical/bacteriological sample submitted to Department? Yes . . . No **X** . . . If yes, mo/day/yr sample was submitted
 Water Well Disinfected? Yes **X** No

5 TYPE OF BLANK CASING USED: 1 Steel 2 PVC 3 RMP (SR) 4 ABS 5 Wrought iron 6 Asbestos-Cement 7 Fiberglass 8 Concrete tile 9 Other (specify below) CASING JOINTS: Glued **X** Clamped Welded Threaded
 Blank casing diameter .6 in. to 420 ft., Dia . . . in. to . . . ft., Dia . . . in. to . . . ft.
 Casing height above land surface .24 in., weight 2.902 lbs./ft. Wall thickness or gauge No. .280 SDR 21 ft.
 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 2 Brass 3 Stainless steel 4 Galvanized steel 5 Fiberglass 6 Concrete tile 7 PVC 8 RMP (SR) 9 ABS 10 Asbestos-cement 11 Other (specify) 12 None used (open hole)
 SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 2 Louvered shutter 3 Mill slot 4 Key punched 5 Gauzed wrapped 6 Wire wrapped 7 Torch cut 8 Saw cut 9 Drilled holes 11 None (open hole)
 SCREEN-PERFORATED INTERVALS: From .340 ft. to 420 ft., From . . . ft. to . . . ft.
 GRAVEL PACK INTERVALS: From .360 ft. to 420 ft., From . . . ft. to . . . ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other HOLE PLUG
 Grout Intervals: From . . . ft. to 20 ft., From . . . ft. to . . . ft.
 What is the nearest source of possible contamination: 1 Septic tank 2 Sewer lines 3 Watertight sewer lines 4 Lateral lines 5 Cess pool 6 Seepage pit 7 Pit privy 8 Sewage lagoon 9 Feedyard 10 Livestock pens 11 Fuel storage 12 Fertilizer storage 13 Insecticide storage 14 Abandoned water well 15 Oil well/Gas well 16 Other (specify below)
 Direction from well? **Northeast** How many feet? **300**

LITHOLOGIC LOG			PLUGGING INTERVALS		
FROM	TO		FROM	TO	
0	2	CLAY	221	225	CLAY
2	50	CLAY	225	247	SANDY CLAY
50	66	SAND	247	260	SAND
66	69	CLAY	260	370	COARSE SAND
69	79	SAND	370	420	COARSE SAND & MED. GRAVEL
79	116	CLAY			
116	148	SANDY CLAY			
148	162	SAND			
162	167	CLAY			
167	170	SANDY CLAY			
170	186	CLAY & SANDY CLAY			
186	189	CLAY			
189	196	COARSE SAND			
196	205	CLAY			
205	221	SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 12-15-94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **KWCL-430**. This Water Well Record was completed on (mo/day/yr) 12-15-94 under the business name of **HOWARD DRIG. CO. BOX 806 BEAVER, OK 73932** by (signature) *Howard Drig.*

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.