

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 065 MORTON SE 1/4 SW 1/4 SW 1/4 19 T 31 S R 39 W

Distance and direction from nearest town or city street address of well if located within city?

APPROX. 9 1/4 MILES EAST & 5 MILES NORTH OF RICHFIELD

2 WATER WELL OWNER: KENNETH PRICE

RR#, St. Address, Box # :

Board of Agriculture, Division of Water Resources

City, State, ZIP code : ROLLA, KS 67954-

Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 236 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \				
1	NW		NE	
M				
i	W			E
l				
e				
	SW		SE	
\ /				
	X			

WELL'S STATIC WATER LEVEL 140 ft. below land surface measured on mo/day/yr 12/07/94  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9.875 in. to 236 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: GLUED

Blank casing diameter 5 in. to 236 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 176 ft. to 236 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 236 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT

Grout intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well? How many feet? 0

FROM TO LITHOLOGIC LOG

FROM TO PLUGGING INTERVALS

0	1	02 SILT
1	13	03 SILTY CLAY 04 SANDY CLAY
13	22	01 CLAY 04 SANDY CLAY
22	30	07 FINE SAND
30	38	04 SANDY CLAY 01 CLAY
38	46	04 SANDY CLAY 36 GYP ROCK
46	50	04 SANDY CLAY
50	62	36 GYP ROCK 04 SANDY CLAY
62	73	04 SANDY CLAY 01 CLAY 07 FINE SAND
73	83	04 SANDY CLAY 05 SAND

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was

completed on (mo/day/year) 12/07/94 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 12/13/94

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number  
 COUNTY: 065 MORTON : SE 1/4 SW 1/4 SW 1/4 : 19 : T 31 S : R 39 W

2 WATER WELL OWNER: KENNETH PRICE

RR#, St. Address, Box # :

Board of Agriculture, Division of Water Resources

City, State, ZIP code : ROLLA, KS 67954-

Application Number:

FROM	TO	LITHOLOGIC LOG
83	101	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
101	110	04 SANDY CLAY
110	121	36 GYP ROCK 04 SANDY CLAY 20 LIMESTONE
121	156	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
156	167	01 CLAY 04 SANDY CLAY 36 GYP ROCK
167	172	28 ROCK 09 COARSE SAND
172	181	31 CALICHE 23 SANDSTONE
181	183	20 LIMESTONE
183	190	31 CALICHE
190	206	23 SANDSTONE 31 CALICHE
206	222	06 VERY FN SAND
222	236	06 VERY FN SAND 07 FINE SAND 08 MEDIUM SAND
236	241	31 CALICHE
241	246	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/07/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/13/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)

*Bruce J. Leichman*