

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 017 COMANCHE SW 1/4 NE 1/4 SW 1/4 9 T 32 S R 17 W

Distance and direction from nearest town or city street address of well if located within city?  
 8 E, 1 S. OF COLDWATER, KS.

2 WATER WELL OWNER: BRANDT DRILLING 173  
 RR#, St. Address, Box #: 107 N.MARKET SUITE 914 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: WICHITA, KS 67202- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 140 ELEVATION:  
 Depth(s) Groundwater Encountered 1. 62 ft. 2. ft. 3. ft.  
 WELL'S STATIC WATER LEVEL 62 ft. below land surface measured on mo/day/yr  
 Pump testdata: Well water was ft. after hours pumping gpm  
 Estimated Yield gpm: Well water was ft. after hours pumping gpm  
 Bore Hole Diameter 8.75 in. to 140 ft., and in. to ft.  
 WELL WATER TO BE USED AS: 06 OIL FIELD  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 120 ft., Dia in. to ft., Dia in. to ft.  
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 120 ft. to 140 ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 140 ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From ft. to 25 ft., From ft. to ft., From ft. to ft.  
 What is the nearest source of possible contamination: 15 OIL/GAS WELL  
 Direction from well? SE How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	5	TAN CLAY			
5	14	05 SAND AND 17 GRAVEL			
14	16	TAN CLAY			
16	48	05 SAND AND 17 GRAVEL			
48	55	TAN CLAY			
55	62	05 SAND AND 17 GRAVEL			
62	65	TAN CLAY			
65	76	05 SAND AND 17 GRAVEL			
76	82	TAN CLAY			
82	140	SAND & CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/16/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 11/30/92 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse